

ORIGINAL

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

KCC

Form ACO-1  
September 1999  
Form Must Be Typed

CONFIDENTIAL

WELL COMPLETION FORM

MAY 31 2001

WELL HISTORY - DESCRIPTION OF WELL & LEASE

CONFIDENTIAL

Operator: License # 4058  
Name: AMERICAN WARRIOR INC.  
Address: PO.BOX 399,  
City/State/Zip: GARDEN CITY, KS., 67846  
Purchaser: \_\_\_\_\_  
Operator Contact Person: KEVIN WILES SR. **RELEASED**  
Phone: (620) 275-2963  
Contractor: Name: DUKE DRLG. **JUN 10 2002**  
License: 5929  
Wellsite Geologist: ALAN DOWNING **FROM CONFIDENTIAL**

Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  SWD  SIOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expt., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_

Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening  Re-perf.  Conv. to  SWD  
 Plug Back 5818' Plug Back Total Depth \_\_\_\_\_  
 Commingled Docket No. \_\_\_\_\_  
 Dual Completion Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?) Docket No. \_\_\_\_\_

4-11-01 4-23-2001 5-2-2001  
Spud Date or Date Reached TD Completion Date or Recompletion Date

API No. 15 - 033-21,216-0000  
County: COMANCHE 10'E OF  
C S1 SW Sec. 13 Twp. 32S S. R. 19W  East  West  
610' feet from (S) N (circle one) Line of Section  
1330' feet from E (W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE NW (SW)  
Lease Name: LAKE Well #: 4

Field Name: UNNAMED  
Producing Formation: VIOLA

Elevation: Ground: 2021' Kelly Bushing: 2034'  
Total Depth: 5850' Plug Back Total Depth: 5818'  
Amount of Surface Pipe Set and Cemented at 611' Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set \_\_\_\_\_ Feet  
If Alternate II completion, cement circulated from \_\_\_\_\_  
feet depth to \_\_\_\_\_ w/ \_\_\_\_\_ sx cmt.

Drilling Fluid Management Plan See 81 B-20-02  
(Data must be collected from the Reserve Pit)  
Chloride content 16,000 ppm Fluid volume 650 bbls  
Dewatering method used HAULED OFF-SITE

Location of fluid disposal if hauled offsite: \_\_\_\_\_  
Operator Name: AMERICAN WARRIOR INC.  
Lease Name: BUNNELL#2 License No. 4058  
Quarter W/2 Sec. 29 Twp. 32S S. R. 18W  East  West  
County: COMANCHE Docket No.: NA

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 31 2001

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: \_\_\_\_\_  
Title: PRODUCTION SUPT. Date: 5-24-2001  
Subscribed and sworn to before me this 25 day of May 2001  
Notary Public: Debra Purcell  
Date Commission Expires: 11/4/03

**DEBRA J. PURCELL**  
Notary Public - State of Kansas  
My Appt. Expires 11/4/03

**KCC Office Use ONLY**  
 Letter of Confidentiality Attached  
If Denied, Yes  Date: \_\_\_\_\_  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

ORIGINAL

Operator Name: AMERICAN WARRIOR INC. Lease Name: LAKE Well #: 4

Sec. 13 Twp. 32S S. R. 19W East West County: COMANCHE 10'E OF

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (es) [X] No

(Attach Additional Sheets)

Samples Sent to Geological Survey [ ] Yes [X] No

Cores Taken [ ] Yes [X] No

Electric Log Run [X] Yes [ ] No

(Submit Copy)

List All E. Logs Run: CDR, DL, CAL, SOINC

[ ] Log Formation (Top), Depth and Datum [X] Sample

Name	Top	Datum
HEEBNER	4270'	-2239
LANSING	4384'	-2408
DRUM	4656'	-2828
BKC	4907'	-2880
MARMATON	4920'	-2892
PAWNEE	5005'	-2974
FORT SCOTT	5042'	-3012
MSS	5112'	-3088
VIOLA	5690'	-3660

CASING RECORD

[ ] New [X] Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./ Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
SURFACE	12-1/4"	8-5/8"	28#	611'	CLASS "A"	325	3%CC, 2%GEL
PRODUCTION	7-7/8"	5-1/2"	17#	5850'		150	D-AIR, GASTOP

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
[X] Perforate [ ] Protect Casing [ ] Plug Back TD [ ] Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	5722'5732'	NONE	611'
			5850'

TUBING RECORD Size 2/38" Set At 5720' Packer At Liner Run [ ] Yes [X] No

Date of First, Resummed Production, SWD or Entr. SI Producing Method [X] Flowing [ ] Pumping [ ] Gas Lift [ ] Other (Explain)

Estimated Production Per 24 Hours Oil Bbls. X Gas Mcf X Water Bbls. SI Gas-Oil Ratio Gravity

Disposition of Gas [ ] Vented [X] Sold [ ] Used on Lease (If vented, Sumit ACO-18.) METHOD OF COMPLETION [ ] Open Hole [X] Perf. [ ] Dually Comp. [ ] Commingled NA [ ] Other (Specify)



CHARGE TO: *American Warrior*  
 ADDRESS: *P.O. Box 399*  
 CITY, STATE, ZIP CODE: *Garden City, Ks*

TICKET No 3460

PAGE 1 OF 4

SERVICE LOCATIONS: 1. *Ness City, Ks*  
 WELL/PROJECT NO.: *24* LEASE: *Sub* COUNTY/PARISH: *Comanche* STATE: *Ks* CITY: *Ness City, Ks* DATE: *4-23-01* OWNER: *son*  
 2. TICKET TYPE:  SERVICE  SALES CONTRACTOR: *Duke rig #17* RIG NAME/NO.: *5160 of Cal Jack* ORDER NO.: *CONFIDENTIAL*  
 3. WELL TYPE: *Oil* WELL CATEGORY: *Development* JOB PURPOSE: *new well long string* WELL PERMIT NO.: WELL LOCATION: *KCC*  
 4. REFERRAL LOCATION: INVOICE INSTRUCTIONS:

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		UNIT PRICE	AMOUNT
		LOC	ACCT	DF		QTY.	U/M		
<i>575</i>		<i>1</i>			<i>MILEAGE 21.04</i>	<i>70</i>	<i>ms</i>	<i>2.50</i>	<i>175.00</i>
<i>578</i>		<i>1</i>			<i>Pump Charge</i>	<i>1</i>	<i>ea</i>	<i>1200.00</i>	<i>1200.00</i>
<i>280</i>		<i>1</i>			<i>Flocheck</i>	<i>850</i>	<i>gal</i>	<i>1.50</i>	<i>1275.00</i>
<i>407</i>		<i>1</i>			<i>Insert float shoe w/ fill up Assy</i>	<i>1</i>	<i>ea</i>	<i>200.00</i>	<i>200.00</i>
<i>406</i>		<i>1</i>			<i>Latch down plug and baffle</i>	<i>1</i>	<i>ea</i>	<i>200.00</i>	<i>200.00</i>
<i>402</i>		<i>1</i>			<i>Centralizers</i>	<i>10</i>	<i>ea</i>	<i>40.00</i>	<i>400.00</i>
<i>403</i>		<i>1</i>			<i>Cement Baskets</i>	<i>2</i>	<i>ea</i>	<i>110.00</i>	<i>220.00</i>
<i>330</i>		<i>1</i>			<i>SMOC Cement</i>	<i>150</i>	<i>sk</i>	<i>9.50</i>	<i>1425.00</i>
<i>287</i>		<i>1</i>			<i>Gussets</i>	<i>300</i>	<i>lb</i>	<i>4.50</i>	<i>1350.00</i>
<i>285</i>		<i>1</i>			<i>From <del>Comanche</del> CFR-1</i>	<i>71</i>	<i>lb</i>	<i>2.75</i>	<i>195.25</i>
<i>290</i>		<i>1</i>			<i>DeArr - 1</i>	<i>71</i>	<i>lb</i>	<i>2.75</i>	<i>195.25</i>
<i>581/583</i>		<i>1</i>			<i>Service Charge of Drayage</i>	<i>150</i>	<i>slb</i>	<i>1.00</i>	<i>150.00</i>
								<i>75</i>	<i>404.57</i>

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.  
 MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS  
 X *[Signature]*  
 DATE SIGNED: *4-20-01* TIME SIGNED: *10:00*  A.M.  P.M.

REMIT PAYMENT TO:  
 SWIFT SERVICES, INC.  
 P.O. BOX 466  
 NESS CITY, KS 67560  
 785-798-2300

SURVEY:  AGREE  UN-DECIDED  DIS-AGREE  
 OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?  
 WE UNDERSTOOD AND MET YOUR NEEDS?  
 OUR SERVICE WAS PERFORMED WITHOUT DELAY?  
 WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?  
 ARE YOU SATISFIED WITH OUR SERVICE?  
 YES  NO  
 CUSTOMER DID NOT WISH TO RESPOND  
 FROM CONFIDENTIAL  
 PAGE TOTAL: *7390.05*  
 JUN 10 2002  
 TOTAL: *267.56*  
 RELEASED  
 TOTAL: *7657.63*

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR: *[Signature]* APPROVAL:

Thank You

JOB LOG

SWIFT Services, Inc.

DATE 4-23-01 PAGE NO. 11

CUSTOMER American Warrior WELL NO. # 4 LEASE Lake JOB TYPE Long Stray TICKET NO. 3460

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
1	12:00							Called out
	22:00							On location / setup
	22:20							Log layed down
	22:40							Change over to run pipe
	23:10							Start log in hole
	03:45							Log on bottom
	03:50							Hooked up & circulate
	04:15							Done circulating
	04:25							Plug rat hole & mouse hole w/ 25 sf
	04:18	4	18					Run 850 gal Flocheck
	04:22	5	5.18					run 150 sf SMD w/ 20 ga step
	04:33							1/2 Flocheck, 1/2 ACERL, 1/2 Densol
	04:50							Done mixing cement
	04:54							wash out pump & line
	04:55							Drop plug
	04:55							Started displacement
	05:00	6	13.5			800		Done w/ displacement
	05:00					1100		Install plug at PS2
						11000		Release pressure
						0		Float hold - latch down bell
								Washed up
								Racked up
	05:15							Job complete
								Shut in
								Set down

**ORIGINAL**

**CONFIDENTIAL**

RELEASED

JUN 10 2002

FROM CONFIDENTIAL

KCC

MAY 31 2001

CONFIDENTIAL

T. Fuchs  
 W. Wells  
 S. Bond  
 104  
 301-503

**ORIGINAL**  
**ALLIED CEMENTING CO., INC.**

7272

Federal Tax I.D.# 48-0727860

TO P.O. BOX 31  
 RUSSELL, KANSAS 67065

**CONFIDENTIAL**

MAY 31 2001

SERVICE POINT:

*Med Lodge*

DATE <i>4-11-01</i>	SEC <i>13</i>	TWP. <i>32S</i>	RANGE <i>19W</i>	CALLED OUT <i>10:00</i>	ON LOCATION <i>12:30</i>	JOB START <i>2:30</i>	JOB FINISH <i>3:15</i>
LEASE <i>Lake</i>	WELL # <i>4</i>	LOCATION <i>Coldwater Lake Ext. S-4</i>			COUNTY <i>Comanche</i>	STATE <i>KS</i>	
OLD OR <u>NEW</u> (Circle one)			<i>W-4 to Rig</i>				

CONTRACTOR *Duke Dely #7*  
 TYPE OF JOB *Conductor*  
 HOLE SIZE *17 1/2* T.D. *298*  
 CASING SIZE *13 3/8 46#* DEPTH *297*  
 TUBING SIZE DEPTH  
 DRILL PIPE DEPTH  
 TOOL DEPTH  
 PRES. MAX MINIMUM  
 MEAS. LINE SHOE JOINT  
 CEMENT LEFT IN CSG. *20 ft.*  
 PERFS.  
 DISPLACEMENT *44 bbls*

**EQUIPMENT**

PUMP TRUCK CEMENTER *LARRY STORM*  
 # *399-265* HELPER *MIKE RUCKER*  
 BULK TRUCK  
 # *353-250* DRIVER *DAVID F.*  
 BULK TRUCK  
 # DRIVER

OWNER *AMERICAN WARRIOR*  
 CEMENT  
 AMOUNT ORDERED *225 65:35:6 + 3% CACL2 + 1/4# Flo-Seal 100 sks CLASS A + 3% CACL2 + 2% Gel*

COMMON	<i>100</i>	@	<i>6.35</i>	<i>635.00</i>
POZMIX		@		
GEL	<i>2</i>	@	<i>9.50</i>	<i>19.00</i>
CHLORIDE	<i>11</i>	@	<i>28.00</i>	<i>308.00</i>
<i>ALW</i>	<i>225</i>	@	<i>6.00</i>	<i>1350.00</i>
<i>FLO-SEAL 56#</i>		@	<i>1.40</i>	<i>78.40</i>
		@		
		@		
HANDLING	<i>350</i>	@	<i>1.05</i>	<i>367.50</i>
MILEAGE	<i>3.50 x 40</i>		<i>.04</i>	<i>560.00</i>
<b>RELEASED</b>				
				TOTAL <i>3317.90</i>

JUN 10 2002

**REMARKS:**

*Broke Circulation Rotary Mud-Switched AND MIXED 225 65:35:6 + 3% CACL2 + 1/4# Flo-Seal. triled with 100sks A + 3% CACL2 + 2% Gel. Displaced plug with 44 bbls Freshwater. Circulated Cement to Surface.*

**FROM CONFIDENTIAL SERVICE**

DEPTH OF JOB	<i>297'</i>		
PUMP TRUCK CHARGE			<i>470.00</i>
EXTRA FOOTAGE		@	
MILEAGE	<i>40</i>	@	<i>3.00 120.00</i>
PLUG 1-13 3/8 TWP		@	<i>70.00 70.00</i>
		@	
		@	
TOTAL <i>660.00</i>			

CHARGE TO: *AMERICAN WARRIOR*  
 STREET *P.O. Box 399*  
 CITY *GARDEN CITY* STATE *KANSAS* ZIP *67846*

**FLOAT EQUIPMENT**

<i>1- BASKET</i>	@	<i>250.00</i>	<i>250.00</i>
	@		
	@		
	@		
	@		
TOTAL <i>250.00</i>			

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE *Kenneth McGuire*

TAX \_\_\_\_\_  
 TOTAL CHARGE *4227.90*  
 DISCOUNT *422.79* IF PAID IN 30 DAYS  
*3805.11*  
 KENNETH M'GUIRE  
 PRINTED NAME

# ALLIED CEMENTING CO., INC.

7273

Federal Tax I.D.# 48-0727860

P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

MED Lodge

DATE <u>4-12-01</u>	SEC. <u>13</u>	TWP <u>32S</u>	RANGE <u>19W</u>	CALLED OUT <u>2:00</u>	ON LOCATION <u>4:30 AM</u>	JOB START <u>7:50 AM</u>	JOB FINISH <u>8:45 AM</u>
LEASE <u>Lake</u>	WELL# <u>4</u>	LOCATION <u>Caldwatechake Ent. 4 S</u>			COUNTY <u>Comanche</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)		<u>4W 1/8 N</u>					

CONTRACTOR Duke #7

TYPE OF JOB Surface Pipe ✓

HOLE SIZE 12 1/4" T.D. 615

CASING SIZE 8 5/8" 24" DEPTH 615

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT 40

CEMENT LEFT IN CSG. 40

PERFS. \_\_\_\_\_

DISPLACEMENT 36.31 bbls

EQUIPMENT

OWNER American Warrior

CEMENT

AMOUNT ORDERED 225 65/35 ilb + 3%

CA 12 1/4" Flo-Seal 100 sks Class A

+ 3% CA 12 1/4" + 3% Seal

COMMON A	100	@	6.35	635.00
POZMIX		@		
GEL	2	@	9.50	19.00
CHLORIDE	11	@	28.00	308.00
AW	225	@	6.00	1350.00
FLO-SEAL	56#	@	1.40	78.40
		@		
		@		
HANDLING	350	@	1.05	367.50
MILEAGE	350 x 40		.04	560.00

RELEASED

TOTAL 3377.90

JUN 10 2002

REMARKS:

FROM CONFIDENTIAL SERVICE

Broke Circulation Rotary Mud

Rumped 5 bbls Freshwater started

Cement 225 sks 65/35 ilb + 3% + 4

Wiped with 100 sks A + 3 + 2 - DPs

Placed 37 bbls Freshwater to land

Plug - Pump to 800# shut Plug

Continue FW Circulation Cement

to Surface.

DEPTH OF JOB	<u>611'</u>			
PUMP TRUCK CHARGE	<u>0-300'</u>			<u>470.00</u>
EXTRA FOOTAGE	<u>311'</u>	@	<u>.43</u>	<u>133.73</u>
MILEAGE	<u>40</u>	@	<u>3.00</u>	<u>N/C</u>
PLUG	<u>1-8 5/8 TRP</u>	@	<u>90.00</u>	<u>90.00</u>
		@		
		@		

TOTAL 693.73

CHARGE TO: American Warrior

STREET P.O. Box 399

CITY GARDEN CITY STATE KANSAS ZIP 67846

FLOAT EQUIPMENT

1 - BAFFLE PLATE	@	45.00	45.00
2 - BASKET	@	180.00	360.00
	@		
	@		
	@		

TOTAL 405.00

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE 4416.63

DISCOUNT 441.67 IF PAID IN 30 DAYS

SIGNATURE Kenneth McGuire

3974.96

KEENNETH MCGUIRE

PRINTED NAME