

CONFIDENTIAL

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 5254
Name: MIDCO Exploration, Inc. **KCC**
Address: 414 Plaza Dr. -- Suite 204 **NOV 21 2000**
City/State/Zip: Westmont, IL 60559
Purchaser: _____
Operator Contact Person: Earl J. Joyce, Jr.
Phone: (630) 655-2198
Contractor: Name: Duke Drilling Co., Inc.

License: 5929
Wellsite Geologist: N/A
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Ab
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: Hall-Jones **11-27-2000**

Well Name: Parcel #1
Original Comp. Date: 12/63 Original Total Depth: 5664'
 Deepening Re-perf. Conv. to Enhr/SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

10-08-00 10-11-00 10/24/00
Spud Date or Date Reached TD Completion Date or Recompletion Date

API No. 15 - 033-00099-0001
County: Comanche County, Kansas
C SE NW Sec. 36 Twp. 32 S. R. 18 East West
1980 feet from S N (circle one) Line of Section
2130 feet from E W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Parcel "OWWO" Well #: 1-36

Field Name: Wildcat
Producing Formation: N/A
Elevation: Ground: 1960' Kelly Bushing: 1965'
Depth: 5784' Plug Back Total Depth: 4904'
Amount of Surface Pipe Set and Cemented at existing 281 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan D&A gH 2/12/01
(Data must be collected from the Reserve Pit)
Chloride content 70,000 ppm Fluid volume 320 bbls
Dewatering method used Steel pits used; vacuumed water
before putting mud in pits
Location of fluid disposal if hauled offsite: _____

Operator Name: Star Resources
Lease Name: Courier 2-9 License No.: 32389
Quarter E/2 Sec. 20 Twp. 32 S. R. 18 East West
County: Comanche Docket No.: D-27668

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: _____
Title: Vice-President Date: 11/21/2000

Subscribed and sworn to before me this 21st day of November, 2000

Notary Public: Nancy L. Macyunas

Date Commission Expires: _____

"OFFICIAL SEAL"
NANCY L. MACYUNAS
Notary Public, State of Illinois
My Commission Exp. 06/24/2002

KCC Office Use ONLY

- Letter of Confidentiality Attached
- If Denied, Yes Date: _____
- Wireline Log Received
- Geologist Report Received
- UIC Distribution

KCC

NOV 27 2000
KANSAS CORPORATION COMMISSION
Wichita, Kansas

NOV 21 2000
RELEASED
FROM CONFIDENTIAL

X

CONFIDENTIAL

Slide Two

15-033-00099-08-01

ORIGINAL

Operator Name: MIDCO Exploration, Inc. Lease Name: Parcel "OWWO" Well #: 1-36

Sec. 36 Twp. 32 S. R. 18 East West County: Comanche County, Kansas

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets) [] Yes [X] No
Samples Sent to Geological Survey [] Yes [X] No
Cores Taken [] Yes [X] No
Electric Log Run (Submit Copy) [X] Yes [] No
List All E. Logs Run: Gamma Ray/Neutron Log, Sonic Bond Log

Table with columns: Log Formation (Top), Depth and Datum, Sample Name, Top, Datum. Includes entries for Heebner, Douglas, Marmaton, Cherokee, Miss LM, and Kind.

KCC
NOV 21 2000
CONFIDENTIAL

CASING RECORD [X] New [] Used Report all strings set-conductor, surface, intermediate, production, etc.

Table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (In O.D.), Weight Lbs./ Ft., Setting Depth, Type of Cement, # Sacs Used, Type and Percent Additives. Includes rows for existing surface and production.

ADDITIONAL CEMENTING / SQUEEZE RECORD. Table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives. Includes a 'RELEASED' stamp.

PERFORATION RECORD - Bridge Plugs Set/Type. Table with columns: Shots Per Foot, Specify Footage of Each Interval Perforated, Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used), Depth. Includes a 'RECEIVED STATE CORPORATION COMMISSION' stamp.

UBING RECORD. Table with columns: Size, Set At, Packer At, Liner Run [] Yes [] No. Includes 'CONSERVATION DIVISION Wichita, Kansas' stamp.

Date of First, Resumed Production, SWD or Enhr. Producing Method [] Flowing [] Pumping [] Gas Lift [] Other (Explain). Estimated Production Per 24 Hours. Oil N/A Bbls., Gas N/A Mcf, Water N/A Bbls., Gas-Oil Ratio, Gravity.

Disposition of Gas. METHOD OF COMPLETION. Production Interval. [] Vented, [] Sold, [] Used on Lease (If vented, Sumit ACO-18.) [] Open Hole, [] Perf., [] Dually Comp., [] Commingled, [] Other (Specify).

CONFIDENTIAL

15-033-00099-00-01

ORIGINAL

ALLIED CEMENTING CO., INC.

4240

Federal Tax I.D.#

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

NOV 21 2000 SERVICE POINT

CONFIDENTIAL

Med Lodge

DATE	10-16-00	SEC	36	TWP	32S	RANGE	18 W	CALLED OUT	12:00 PM	ON LOCATION	6:30 PM	JOB START	2:00 AM	JOB FINISH	2:45 AM
LEASE	Parcel	WELL #	1-36	LOCATION	160 r willmore Rd 4s			COUNTY	Comanche	STATE	KS				
OLD OR NEW	(Circle one)		to stop sign		34 E 1/2 S										

CONTRACTOR *Duke #4* OWNER *Midco Exploration*

TYPE OF JOB *Production*

HOLE SIZE *7 7/8* T.D. *5784* CEMENT

CASING SIZE *4 1/2* DEPTH *5799* AMOUNT ORDERED *245 SX ASC + 5#*

TUBING SIZE DEPTH *Kol-seal/sack + .3% FI-10*

DRILL PIPE DEPTH *(1000 gals Mud clean 10 BBLs 2% KCL)*

TOOL DEPTH

PRES. MAX MINIMUM COMMON @

MEAS. LINE SHOE JOINT *42,10* POZMIX @

CEMENT LEFT IN CSG: GEL @

PERFS: CHLORIDE @

DISPLACEMENT *92 1/2 2% KCL* ASC *245* @ *8.20* *2009.00*

EQUIPMENT

PUMP TRUCK CEMENTER *Justin Hart* *CLAPRO 10 GALS* @ *22.90* *229.00*

233-302 HELPER *Shane Winsor* *MUD CLEAN 1000 GALS* @ *.75* *750.00*

BULK TRUCK HANDLING *3.13* @ *1.05* *328.65*

301 DRIVER *David Felio* MILEAGE *31.3 x 42* @ *.04* *525.84*

RELEASED

TOTAL *4808.24*

NOV 21 2001

REMARKS:

Pipe on Bottom Drop Ball Break

Circ for Pump 1000 gals Mud

Clean 10 BBLs 2% KCL Mix 245

sx ASC @ 14.5# shut down wash

up pump r lines Release Plug Start

Disp. @ 7 BPM 1/4 pressure @ 48

BBLs slow Rate 5 BPM 700 BBLs slow

Rate 4 BPM 85 BBLs slow Rate 3 BPM 92 1/2

BBLs Bump Plug 1100# to 1750# Float Held

FROM CONFIDENTIAL SERVICE

DEPTH OF JOB *5799*

PUMP TRUCK CHARGE *1378.00*

EXTRA FOOTAGE @

MILEAGE *42* @ *3.00* *126.00*

PLUG *4 1/2" TRP* @ *38.00* *38.00*

TOTAL *1542.00*

CHARGE TO: *Midco Exploration*

STREET

CITY STATE ZIP

FLOAT EQUIPMENT

4 1/2 - 1- Guide shoe 125.00 125.00

1- AFU Insert @ 210.00 210.00

1- Stop Ring @ 20.00 20.00

10- Turbo centralizers @ 55.00 550.00

14- Reg Centralizers @ 45.00 630.00

TOTAL *1535.00*

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX

TOTAL CHARGE *1788.24*

DISCOUNT *788.53* IF PAID IN 30 DAYS

709.71

SIGNATURE *David H Mayfield*

SIGNATURE *David H Mayfield*

PRINTED NAME

CONFIDENTIAL

ALLIED CEMENTING CO., INC.

ORIGINAL

4503

Federal Tax I.D.#

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

15-033-00099-00-0 NOV 21 2000

SERVICE POINT:

Medicine Lodge

CONFIDENTIAL

DATE 10-24-00	SEC. 36	TWP. 32s	RANGE 18w	CALLED OUT 12:30 pm	ON LOCATION 2:30 pm	JOB START 3:00 pm	JOB FINISH 4:30 pm
LEASE Parcel	WELL# 1-36	LOCATION 160 + Wilmore Rd. 4s		COUNTY Comanche		STATE KS.	
OLD OR <u>NEW</u> (Circle one)			3/4 w, 2s,				

CONTRACTOR Jet well service.

OWNER Midco Exploration

TYPE OF JOB OHP

HOLE SIZE	T.D.
CASING SIZE	DEPTH
TUBING SIZE 2 3/8	DEPTH 1012
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX 100	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	Freshwater.

CEMENT

AMOUNT ORDERED	110 sx 60:40:6
	15 sx 6el USED 5sx

COMMON	66	@ 6.35	419.10
POZMIX	44	@ 3.25	143.00
GEL	11	@ 9.50	104.50
CHLORIDE		@	
		@	
		@	
		@	
		@	
		@	
		@	
HANDLING	121	@ 1.05	127.05
MILEAGE	121 x 42	.04	203.28

EQUIPMENT

PUMP TRUCK #352	CEMENTER Carl Balding
	HELPER Stane Winsor
BULK TRUCK #242	DRIVER Mike Rucker
BULK TRUCK #	DRIVER

RELEASED

TOTAL 996.93

NOV 21 2001

REMARKS:

SERVICE

FROM CONFIDENTIAL:

1st plug 1012 feet load hole with 5 sx 6el water, pump 50 sx cement Displace with 2 BBS Fresh water.

2nd plug 300 feet load hole with freshwater, pump 50 sx cement, Disp w/ 1/4 BBS.

3rd plug, pump 10 sx - 40 feet

DEPTH OF JOB	1012
PUMP TRUCK CHARGE	450.00
EXTRA FOOTAGE	@
MILEAGE	42 @ 3.00 126.00
PLUG	@
	@
	@

TOTAL 576.00

CHARGE TO: Midco Exploration

STREET _____
CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

TOTAL _____

TAX	
TOTAL CHARGE	1572.93
DISCOUNT	157.30 IF PAID IN 30 DAYS
	1415.63

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE David H. Mayfield

DAVID H. MAYFIELD
PRINTED NAME