

TATE OF KANSAS  
TATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-044-21030 <sup>~033-21030-00-10</sup>

LEASE NAME Swayze Twin

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

420 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 17 TWP. 31S RGE. 19W (E) or (W)

COUNTY Comanche

LEASE OPERATOR BLACK PETROLEUM COMPANY

ADDRESS P.O. Box 12922 Wichita, Kansas 67277-2922

PHONE (316) 729-8220 OPERATORS LICENSE NO. 30407

Date Well Completed \_\_\_\_\_

Character of Well Gas

Plugging Commenced 12-13-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-15-00

The plugging proposal was approved on \_\_\_\_\_ (date)

by Steve Middleton (KGC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5248'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD | KANSAS CORPORATION COMMISSION

RECEIVED  
12-28-2000  
DEC 28 2000

Formation	Content	From	To	Size	Put In	Pulled out
				13-3/8"	302'	None
				8-5/8"	679'	None
				5-1/2"	5247'	4000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 4860' and 5 sks. cement. Shot pipe @ 4200' and 4000', pulled up to 1100', pumped 15 sks. gel and 50 sks. cement, pulled to 690', pumped 50 sks. cement, pulled up to 40' and pumped 10 sks. cement. 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Black Petroleum Company

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
statements, and matters herein contained and the log of the above-described well as filed to  
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 26th day of December, 2000

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

