

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-21,272-C000

LEASE NAME Eckles #3-2

WELL NUMBER \_\_\_\_\_

SPOT LOCATION SW NE of NW

SEC. 2 TWP. 30s RGE. 13w (E) or (W)

COUNTY Berber

Date Well Completed \_\_\_\_\_

Plugging Commenced 2/24/84

Plugging Completed 3/5/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS 6427 E. Kellogg, Wichita, Ks. 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. # 5056

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4586'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	348'	none
				4 1/2"	2960'	1728'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mixed 1 sack hulls, with 30 sacks common cement & pumped to 2000'. Shot pipe at 1800' & 1700'. Pulled 42 joints of pipe. Plugged well with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug, & 150 sacks 60/40 poz 2% gel 3/2 c.c.  
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

STATE CORPORATION COMMISSION

MAR 12 1984  
3-12-84  
CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 9th day of March, 19 84

IRENE HOOVER  
State of Kansas  
My Comm. Exp. Aug. 15, 1985

Irene Hoover  
Notary Public

My Commission expires: \_\_\_\_\_

KANSAS DRILLERS LOG

COMPANY F. G. Holl

SEC. 2 T. 30S R. 13W

FARM Eckles

NO. 3-2

LOC. SW NE NW

COUNTY Barber

ROTARY TOTAL DEPTH 4,586'

COMM. September 26, 1981

COMP. October 7, 1981

CONTRACTOR H-30, INC. (Rig#2)

ISSUED October 15, 1981

CASING

10 3/4"

8 5/8" Set at 348' cemented w/325 sxs cement

5 1/2"

4 1/2" Set at 2953' cemented w/100 sxs cement

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS


Sand	50'
Red Bed and Shale	350'
Shale	1,805'
Shale and Lime	2,573'
Lime and Shale	3,010'
Shale	3,230'
Shale and Lime	3,825'
Lime and Shale	4,060'
Lime	4,224'
Lime and Shale	4,330'
Lime	4,470'
Lime and Shale	4,505'
Shale and Sand	4,509'
Lime	4,586'
Rotary Total Depth	4,586'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

*Gary Younger*  
Gary Younger - V. President

State of Kansas )  
                  ) ss:  
County of Sedgwick )

Subscribed and Sworn to before me a Notary Public in and for said county and state this 15th day of October, 1981.



*Helen Pracht*  
Helen Pracht - Notary Public

My Commission Expires

June 4, 1985