

API NUMBER 15-007-28762-0000

LEASE NAME Eckles

WELL NUMBER 2-2

SPOT LOCATION SE NE NW

SEC. 2 TWP. 30S RGE. 13W (E) or (W)

COUNTY Barber

Date Well Completed _____

Plugging Commenced 4-23-86

Plugging Completed 4-29-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS 6427 E. Kellogg, Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	190'	none
				4-1/2"	4639.5'	3239'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4305' and 4 sacks cement. Shot pipe @3817', 3509', 3239' and pulled a total of 102 joints of 4-1/2" casing. Plugged surface with 3 hulls, 15 gel, 60 cement, 10 gel, 1 hull, plug and 150 cement, 60/40 pos. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
 Address Box 347 Chase, Kansas 67524


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 6th day of May, 1986



My Commission expires: _____

Irene Hoover
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 07 1986
 5-7-86
 CONSERVATION DIVISION
 Wichita, Kansas

15-007-20762-0000
V L L L L U U

COMPANY F. G. Holl

SEC. 2 T. 30S R. 13W

FARM Eckles

NO. 2-2

LOC. E/2

TOTAL DEPTH 4640'


COUNTY Barber

COMM. 7-2-79

COMP. 7-12-79

CONTRACTOR DaMac Drilling Inc.

CASING 8 5/8 set @ 200



ELEVATION

PRODUCTION 4 1/2 set @ 4639.5

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand, RedBed	0	411
Shale	411	1770
Shale, Lime	1770	4475
Lime	4475	4640

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1986
3-12-86
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } ss

I, Martha J. McKown of DaMac Drilling Inc.

upon oath state the above and foregoing is a true and correct copy of the log of the Eckles No. 2 well.

Martha J. McKown

Subscribed and sworn to before me this 16 day of July 1979

My Commission Expires: 4-28-81

LANA L. REMMER
Barton County, Kansas
My Appl. Exp. 4-28-81

Lana L. Remmer
NOTARY PUBLIC