


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Comanche County, Sec. 6 Twp. 32S Rge. 19 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
C NE NW

Lease Owner KRM Petroleum Corp.  
Lease Name W. J. Robbins Well No. 1  
Office Address 817 Seventeenth St., Denver, COLO. 80202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plot

Dry Hole  
Date Well completed 9-6-78 19  
Application for plugging filed 9-6-78 19  
Application for plugging approved 9-6-78 19  
Plugging commenced 9-6-78 19  
Plugging completed 9-6-78 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well William Owen  
Producing formation Depth to top Bottom Total Depth of Well 6340'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO   | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|------|--------|--------|------------|
|           |         | 0    | 631' | 8 5/8" | 16 jts |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from T.D. to 630' 50 sack cement plug  
mud to 40' 1/2 sacks hulls, plug bridged. 12 sacks  
base cellar, 3 sacks rat hole. By Allied Cementing.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Allied Cementing Co., Pratt, KS.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Kirby C. Evers (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kirby C. Evers  
453 S. Webb Rd., Wichita, KS. 67207  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 78

My commission expires August 20, 1980



RECEIVED  
Virginia Lee Sedgwick  
Notary Public.

SEP 18 1978  
9-18-78  
CONSERVATION DIVISION  
Wichita, Kansas

15-033-20254-0000

COPY

W. J. ROBBINS #1  
C NE NW  
Section 6-32S-19W  
Comanche County, KS.

OPERATOR: KRM PETROLEUM CORPORATION  
CONTRACTOR: XPLOR DRILLING COMPANY  
COMMENCED: 8-19-78  
COMPLETED: 9-6-78

CASING RECORD: Ran surface casing, 8 5/8" 24# 16 jts. new, set @631'  
cement with 450 sacks cement, 250 sacks Lite Weight 2%  
Cal.chloride, 200 sacks Common 2% gel, 3% cal.chloride.

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>ELEVATION</u> |
|------------------|-------------|-----------|------------------|
| Red Bed          | 0           | 1100      |                  |
| Red Bed & Sand   | 1100        | 3550      |                  |
| Line & Shale     | 3550        | 6340      |                  |
| R.T.D.           | 6340        |           |                  |

STATE OF KANSAS )  
 ) SS:  
COUNTY OF SEDGWICK )

I certify that this is a true and correct copy of the Driller's Log of  
the well drilled C NE NW of Section 6-32S-19W, Comanche County, Kansas,  
to the best of my knowledge and belief.

XPLOR DRILLING CO.

*Kirby C. Evers*  
Kirby C. Evers, Vice President

Subscribed and sworn to before me this 11th. day of September, 1978.

MY COMMISSION EXPIRES:  
August 25, 1980

*Virginia Lee Smith*  
Virginia Lee Smith, Notary Public

