

15-033-00019-00-01


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD ¹²

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Comanche County. Sec. 8 Twp. 32S Rge. (E) 19 (W)

Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines SE SE SE
Lease Owner Aladdin Petroleum Corporation
Lease Name Alexander Well No. 1
Office Address 809 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed February 23, 19 63
Application for plugging filed April 14, 19 66
Application for plugging approved April 14, 19 66
Plugging commenced April 18, 19 66
Plugging completed April 21, 19 66
Reason for abandonment of well or producing formation not profitable



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production not produced 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 5312 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				12-1/4"	470	none
				4-1/2"	5316	4741

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled sand 5250' to 5225'.
3 sacks cement 5225 to 5200'.
Pulled 4741' of 4-1/2 inch casing.
Mud 5200 to 300'.
Rock bridge 300' to 290'.
25 sacks cement 290 to 215'.
Mud 215' to 35'.
Rock Bridge and 10 sacks cement 35' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1966
6-14-66
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Glenn & Smith
Address Ellinwood, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.
J. M. Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. M. Johnson J. M. Johnson, Vice Pres.
809 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 1966

Esther L. Marshall
Esther L. Marshall Notary Public.

My commission expires Sept. 19, 1967

Trotex Oil Co. - Owner

Sierra Petroleum Co., - Contr.

ALEXANDER #1

SE SE SE Sec. 8-32S-19W
Commanche County, Kansas

Total Depth: 5312

Elev: 2041 KB

Comm: 10/21/57

Comp: 11/12/57

Casings:

12 1/4" set at 450'

FORMATION	DEPTH
Cement	470
Shale & red bed	1015
Lime	1030
Shale	1280
Shale & salt	1420
Shale & shells	1835
Shale & lime	2095
Shale & gyp	2300
Shale & lime	4497
Lime	4979
Lime & shale	5012
Lime	5190
Miss	5225
Shale & chert	5260
Lime	5293
Miss	5308
Lime	5310
Miss	5312
Tops:	
Elgen	4186
Heebner	4279
Brown Lime	4464
Lansing K. C.	4485
Miss	5160

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Hensler

Subscribed and sworn to before me this 13th day of November, 1957.

Margie Cooper
Notary Public

My commission expires: 1-30-61.

PLUGGING
FILE SEC 8 T 32 R 19W
BOOK PAGE 61 LINE 11

RECEIVED
NOV 14 1957
11-14-57