

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Comanche County. Sec. 1 Twp. 32S Rge. 16W (E)____(W)
C W/2

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Eason Oil Company
Lease Name Schuette Well No. 2-1
Office Address P.O. Box 18755, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 24, 19 66
Application for plugging filed April 24, 19 66
Application for plugging approved April 24, 19 66
Plugging commenced April 24, 19 66
Plugging completed April 24, 19 66
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4876 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	262.77'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud up to 250', 1/2 sack of hulls, plug, 25 sacks of cement. Filled hole up to 40', set plug, 1/2 sack of hulls, 10 sacks of cement. Plugged rathole with 1 sack of hulls and 2 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1966
4-28-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address Box 173 -- Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Maxine V. Starr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Starr
1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of April, 19 66

My commission expires 5-22-66

Dean Holler
Notary Public.

DRILLERS LOG

Schuette No. 2-1

CASING RECORD: 8 5/8" @ 262.77' w/260 ex cement
 COMPANY: Eason Oil Company
 CONTRACTOR: Red Tiger Drilling Company
 COMMENCED: April 8, 1966
 COMPLETED: April 24, 1966
 DESCRIPTION: C W/2
 I-328-16W
 Comanche Co., Ks.
 ELEVATION: 1900 DF
 1903 RB
 TOTAL DEPTH: 4876'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Shells	0	300	
Red Bed & Shale	300	838	
Anhydrite	838	853	
Shale & Shells	853	1075	
Shale	1075	1085	
Shale & Shells	1085	1790	
Shale & Lime	1790	4260	
Lime	4260	4811	
Shale & Chert	4811	4876	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Starr
Maxine V. Starr

Subscribed and sworn to before me this 26th day of April, 1966.

Jean Ables
Notary Public

My Commission Expires:

5-22-66

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 - 1966
CONSERVATION DIVISION
MICHIGAN