

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20194-00-00

LEASE NAME Schuette #1

WELL NUMBER _____

SPOT LOCATION C NW SE

SEC. 2 TWP 32s RGE 16w (E) or (W) (W)

COUNTY Comanche

Date Well Completed _____

Plugging Commenced 2/13/86

Plugging Completed 2/21/86

LEASE OPERATOR Patton Oil Co.

ADDRESS 672 W. 4th, Hoisington, Ks. 67544

PHONE # (316) 653-2277 OPERATORS LICENSE NO. 5992

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4814'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	363'	none
				5 1/2"	4795'	3738'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Pumped bottom with 30 sacks cement, displaced to 4500'. Shot pipe at 4100', 3950', & 3738'. Pulled 92 joints of pipe. Plugged well with 3 hulls, 10 gel, 70 cement, 15 gel, 1 hull, plug, & 150 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or


(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 24th day of February, 1986

My Commission expires:



RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1986

2-26-86
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 01-84