

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Comanche County. Sec. 36 Twp. 31 Rge. (E) 20 (W)

Location as "NE/CNW%SW%" or footage from lines NE NE SW/4

Lease Owner M. B. Armer

Lease Name Lorimer Well No. 1

Office Address 710 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole - Lost Hole

Date well completed Aug. 15, 19 55

Application for plugging filed " " 19 "

Application for plugging approved " " 19 "

Plugging commenced " " 19 "

Plugging completed " " 19 "

Reason for abandonment of well or producing formation Lost Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 1880 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	273'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole with heavy Rotary Mud to 270 ft.
Set plug at 270 ft. and cemented with 20 sacks cement
and 1/3 sack hulls, cemented through drill pipe. Mudded hole
to 35 ft., set plug, 1/3 sack hulls and 10 sacks cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1955
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor M. B. Armer
Address Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
L. C. Sponenberg (employee of owner) or (owner/conservator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of August, 19 55

My commission expires February 13, 1956. Rose Furey Notary Public.

PLUGGING
FILE SEC 36 T 31 R 200
BOOK PAGE 143 LINE 16


KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY M. B. Armer
 FARM Lorimor NO. 1

SEC. 36 T. 31S R. 20W
 LOC. NE NE SW

TOTAL DEPTH 1880'
 COMM. 8/6/55 COMP. 8/16/55
 SHOT OR TREATED
 CONTRACTOR M. B. Armer
 ISSUED

COUNTY Comanche
 KANSAS



CASING
 20 10
 15 8 273'
 12 6
 13 5

ELEVATION
 PRODUCTION Lost Hole

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	190
Sand & Red Bed	225
Red Bed & Gyp	450
Red Bed & Shale	875
Red Bed & Sand	1065
Anhydrite	1075
Shale	1365
Shale, Shells & Salt	1670
Shale & Lime, Broken	1840
Shale & Lime	1846
No returns	1880

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

By *[Signature]*

STATE OF KANSAS
 COUNTY OF SEDGWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 22nd day of August, 1955.

[Signature]
 Notary Public

My Commission expires February 13, 1956.

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 23 1955
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 36 T. 31 S. 20 W
 BOOK PAGE 143 LINE 16