



CP2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burriss of Chief has this

date requested permission to plug the following described well:

Mr. Burriss guarantees payment of the plugging fee.

Operator's full Name: Chief Drlg. Co., & Lee Banks

Complete Address: 905 Century Plaza, Wichita, Kansas

Lease Name: Knoefler Well No. 1

Location: C NE SW Sec. 33 Twp. 21 Rge. 25 (E) (W)

County: Hodgeman Total Depth 4600' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burriss was instructed to plug the well as follows:


8 5/8" to 485' circulated w/ cement. Mud 4600' to 660'

Spot 50 sacks cement 660' to 500' Mud 500' to 450'

Spot 25 sacks cement 450' to 375' Mud 375' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent