



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 4 1974
10-4-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Michael of Search Drlg Co has this

date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: Wayne L. Kirkman

Complete Address: Box 18¹⁴⁸~~148~~ Wichita, KS

Lease Name: Beck-Hoskinson Well No. 1

Location: 1320' WEL & 880' NSL Sec. 36 Twp. 26s Rge. 13 (E) (W) W

County: Pratt Total Depth 3350 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Michael was instructed to plug the well as follows:

360 ft 8 5/8 surface cemented with 325 sacks. Fill hole
to 250 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to 40
ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

Conservation Division Agent