



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 14 1964

4-14-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. W. M. Barnett of D & M Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Barnett guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management Inc.

Complete Address: 1515 Wichita Plaza, Wichita, Kansas

Lease Name: Pepperd Well No. # 1

Location: C NE NW Sec. 2 Twp. 33 Rge. 18 (E) (W) W

County Comanche Total Depth 5850 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Barnett was instructed to plug the well as follows:

508' of 8 5/8" surface pipe, cemented with 400 sacks. Fill hole with drilling mud to 350', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent