



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 15 1965  
 09-15-1965  
 CONSERVATION DIVISION  
 Wichita, Kansas

September 12, 1965.

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. T. F. Brown of Gabert-Jones Drilling Co. has this date requested permission to plug the following described well:

Mr. T. F. Brown guarantees payment of the plugging fee.

Operator's full Name: Magaw & Zimmer

Complete Address: 22 Park Avenue Bldg. Oklahoma, City Okla.

Lease Name: Herd Unit #1 Well No. #1

Location: C-NW-SE Sec. 17 Twp. 32S Rge. 18W (E) (W)

County Comanche County Total Depth 5845' Oil Well

Gas Well  Input Well  SWD Well  D & A \*  Lost Hole

Mr. T. F. Brown was instructed to plug the well as follows:

550' of 8 5/8" surface pipe circulated with cement. Heavy drill mud to 540' cementing plug & 1 sack hulls. 25 sacks cement mud to 40' cementing plug, 1 sack hulls, 10 sacks cement to base of cellar. 2 sacks cement in rathole & 2 sacks cement in mousehole.

Very truly yours,

*Hermon Justus*  
 Conservation Division Agent