



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

30 January 1982

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-033-20533-0000

RECEIVED
STATE CORPORATION COMMISSION
FEB - 2 1982
2-2-82
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Rodney Reynolds of Par Petroleum Co. has

date requested permission to plug the following described well:

Operator's Full Name: Par Petroleum Co., Inc.

Complete Address: P.O. Box 280 Liberal Kansas 67901

Lease Name: Dewall Well No. 1

Location: 75' 50" E - NE - NW Sec. 20 Twp. 32 Rge. 17 (E) (W)

County: Comanche Total Depth: 5275'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Reynolds was instructed to plug the well as follows:

There is 115' of 16" conductor pipe & 600' of 8 1/2" surface pipe
Cement circulated. 1st plug is at 1000' with 40 lbs. of cement.
2nd plug pushed rubber plug to 580' & pumped 35 lbs. of
Cement on top of it. 3rd plug 40' to 0' on solid bridge with
10 lbs. of cement. They pumped 10 lbs. of cement in rat hole
& 5 lbs. of cement in mouse hole. The farmer wants the water
well & was advised what they had to do. The plugging was
accomplished by Halliburton.

Very truly yours,

Paul Lutton

Conservation Division Agent