



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

**VERBAL PERMIT FORM**  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dec. 11, 1962.

RECEIVED  
 STATE CORPORATION COMMISSION  
 12-14-62  
 DEC 14 1962

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. H. C. Hickman of Stickle Drilling Co. has this date requested permission to plug the following described well:

Mr. H. C. Hickman guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil CO.

Complete Address: 321 West Douglas Wichita, Kansas.

Lease Name: John Knackstedt #1 Well No. #1

Location: C-SW-NW Sec. 10 Twp. 30 Rge. 13 (E) (W) X

County Barber County. Total Depth 4740 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. H. C. Hickman. was instructed to plug the well as follows:

325' of 13 3/8" surface pipe circulated with H A-5 cement.  
( 350 sacks). Hole filled to 240' with heavy drill mud, 1/4  
sack hulls, 1st cementing plug and 30 sacks cement. Hole  
filled to 40' with heavy drill mud, 1/4 sack hulls, 2nd  
cementing plug and 20 sacks cement to base of cellar. Rat  
hole bridged and 2 sacks cement.

Very truly yours,

*Herman J. Justice*  
 Conservation Division Agent