

15-033-10026-00-00

FORM - CP-2
Rev. 6-26-62

State of Kansas



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1963
07-18-1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Dick Roby of Petroleum Inc. has this date requested permission to plug the following described well:

Mr. Roby guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name: Blackard Well No. # 1

Location: C NE SW Sec. 15 Twp. 32 Rge. 18 (E) (W) W

County Comanche Total Depth 5210 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Roby was instructed to plug the well as follows:

285' of 8 5/8" surface pipe, cement circulated with 400 sacks.
Fill hole with mud to 275', 1st cementing plug, 1/4 sack hulls,
cement with 20 sacks. Fill hole with mud to 40', 2nd cementing
plug, 1/4 sack hulls, cement with 10 sacks to base cellar.
Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent