



15-033-20185-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
WILLIAM G. GRAY  
Carol J. Larson, Executive Secretary

Governor  
Chairman  
Commissioner  
Commissioner

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Bruck  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Pulley of Rockhold Engineering, Inc. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: The Roxana Corp.

Complete Address: Box 1162 Great Bend, Kansas

Lease Name: Reynolds Well No. #1

Location: C SW NW Sec. 28 Twp. 32 Rge. 18 (E)(W) W

County: Comanche Total Depth 5378' Oil Well

Gas Well X Input Well  SWD Well  D & A  Lost Hole

Mr. Pulley was instructed to plug the well as follows:

502' - 8 5/8" csg w/ 350 sx cement

4 1/2" csg set @ 5310' Plug back to 5226' Perfs 5210' to 5200'

S B w/ bailer to 5175' & 4 sx cement Plug & 50 sx 50/50 poz

6% gel @ 800' 15 gel 8 hulls 10 gel Cemented by Sun

Plug & 40 sx cement @ 500' Pulled 4000' 4 1/2" csg

Bridge & 10 sx @ 40' to 5' below GL Very truly yours,

STAMPED SIP 100#

FEB - 9 1981  
02-09-1981

M. V. Bruck  
Conservation Division Agent