



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1964
03-16-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bill Newport of Hall-Jones Oil Corp. has this

date requested permission to plug the following described well:

Mr. Newport guarantees payment of the plugging fee.

Operator's full Name: Hall-Jones Oil Corporation

Complete Address: 1710 Liberty Bank Bldg., Oklahoma City, Ok.

Lease Name: Parcel Well No. # 1

Location: C SE NW Sec. 36 Twp. 32 Rge. 18 (E) (W) W

County Comanche Total Depth 5663 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Newport was instructed to plug the well as follows:

281' of 8 5/8" surface pipe, cemented with 225 sacks. Fill
hole with drilling mud to 275', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Ewing
Conservation Division Agent