

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-099-30044-0000
Spot: NW/NW/NW/SE Sec 13 Twp 31 S Rng 19 [X] E / [] W
2449 Feet from [] N / [X] S Line of Section
2578 Feet from [X] E / [] W Line of Section
GPS: Lat: 37.347092 Long: 95.276264 Date: 3/13/14
Lease Name: NOLA NOLS SHAW (700 N. 26th St, Parsons) Well #: PAR 01
County: Labette Total Vertical Depth: 608 feet

Operator License No: 101 String Size Depth Pulled Comments
Op Name: KANSAS CORPORATION COMMISSION BORE HOLE
Address 1: 130 S MARKET
Address 2:
City: WICHITA
State: KS Zip Code: 67202

Well Type: GAS - Natural Gas - Production UIC Docket No.: Date/Time to Plug: 3/26/14 /
Plug Co License No.: 33749 Plug Co. Name: KWS
Proposal Rcvd from: MIKE KEPLEY Company Name: KWS Phone: (620) 431-9212

Proposed Plugging Report: CLEAN OUT WELLS TO BOTTOM. PUMP FULL OF PORTLAND CEMENT, INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS, CASING SHOULD BE PERFORATED IN AT LEAST 2 INTERVALS, UNLESS WELL IS DOCUMENTED AS ALT. 2 COMPLETION.

Plugging Proposal Received By: TONY ANDERSON/TOM BILYEU Witness Type: COMP - Complete 100%
Date/Time Plugging Completed: 3/26/14 / KCC Agent: TONY ANDERSON/TOM BILYEU

Actual Plugging Report: Perfs: Top Bottom Thru
TESTED YARD AND DUG AND REMOVED TREES WHERE THE GAS TEST WAS STRONGEST. THE GAS WAS TRAVELING THRU WORM HOLE AND TREE ROOTS. REMOVED DIRT FROM THE YARD TO GET DEEP ENOUGH TO SEE WHERE GAS WAS COMING FROM. DUG DOWN WHERE THE GAS WAS VENTING THE MOST AND FOUND A BOREHOLE 12' DOWN. SET A SURFACE AND CEMENTED IT IN WITH 12 SACKS. DRILLED DOWN TO 608' ON WOOD, BRICKS AND CAVINGS. HIT STEEL AT 608' AND PUMPED 147 SACKS OF CEMENT. THE DIRT WAS HAULED BACK IN AND THE LAWN WAS RESEEDDED.

Remarks: CONTRACT#38595;CONTROL#20140088-001;NAD83;GPS BY TOM,TONY

Plugged Thru: TBG - Tubing RECEIVED KANSAS CORPORATION COMMISSION Plugged Due to Compliance Issue: [] Yes [] No

District: 03 MAY 02 2014 (Technician) Form: District Plugging Report -
CONSERVATION DIVISION WICHITA, KS