

1 090276

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION S/2 SW  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,558 0000  
SW, SEC. 36, T 26 S, R 13 W/E  
660 feet from ~~X~~/S section line  
3960 feet from ~~X~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408  
Operator: Trans Pacific Oil Corporation  
Name & Address One Main Place, Suite 606  
Wichita, KS 67202

Lease Name Beck Well # 1  
County Pratt 141.38  
Well Total Depth 4350 feet  
Conductor Pipe: Size        feet  
Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A X

Other well as hereinafter indicated       

Plugging Contractor Trans-Pac Drilling, Inc. License Number 5841

Address One Main Place, Suite 606, Wichita, KS 67202

Company to plug at: Hour: 4:00 am Day: 21 Month: January Year: 19 85

Plugging proposal received from Leon Strecker

(company name) Trans-Pac (phone) 316-265-0226

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 750' with 50 sx cement

2nd plug at 300' with 40 sx cement

3rd plug <sup>solid bridge</sup> hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by R.B. Arthur  
(TECHNICIAN)

Plugging Operations attended by Agent?: All        Part        None X

Operations Completed: Hour: 6:30 am Day: 21 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 750' with 50 sx cement, 2nd plug at 300' with 40  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to  
circulate mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION

RECEIVED  
JAN 23 1985  
1-23-85  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 1-29-85

Signed R.B. Arthur  
(TECHNICIAN)

ENV NO. 6742

FEB 27 1985

CARD MUST BE TYPED

State of Kansas  
**NOTICE OF INTENTION TO DRILL**  
(see rules on reverse side)

**CORRECTED COPY**

CARD MUST BE SIGNED

Starting Date: January 10, 1985  
month day year

API Number IS- 151-21,558-00-00

OPERATOR: License # 9408  
Name Trans Pacific Oil Corporation  
Address One Main Place, Suite 606  
City/State/Zip Wichita, Kansas 67202  
Contact Person Elfie A. Lacio  
Phone (316) 262-3596

S/2 SW (location) Sec 36 Twp 26 S, Rge 13  East  West

CONTRACTOR: License # 5841  
Name Trans-Pac Drilling, Inc.  
City/State Wichita, Kansas 67202

660' Ft North from Southeast Corner of Section  
3960' Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Nearest lease or unit boundary line 660' feet.  
County Pratt  
Lease Name Beck Well# 1  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

if OWWO: old well info as follows:  
Operator .....  
Well Name .....  
Comp Date ..... Old Total Depth .....  
Projected Total Depth 4400' feet  
Projected Formation at TD Arbuckle  
Expected Producing Formations Arbuckle

Depth to Bottom of fresh water 150 feet  
Lowest usable water formation .....  
Depth to Bottom of usable water ~~390~~ 250 feet  
Surface pipe by Alternate: 1  2   
\* Surface pipe to be set 250 feet  
Conductor pipe if any required: 60 feet  
Ground surface elevation ..... feet MSL  
This Authorization Expires 7-7-85  
Approved By 1-7-85

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging holes to K.C.C. specifications. was: 300' All #1  
Date 1-10-1985 Signature of Operator or Agent [Signature] Title Exec. Vice President  
Howe 1-10-85 set 250' 85P

Form C-1 4/84

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 23 1985  
CONSERVATION DIVISION  
Wichita, Kansas