

1 090026

9-28

159

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,471-0000
NE SE NE, SEC. 5, T 31 S, R 18 W/4

3350 feet from S section line
320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399

Lease Name Robinson Well # 3

Operator: Farrar Pump & Supply

County Comanche 166.21

Name & Address P.O. Box 209

Well Total Depth 5114 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 526

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Farrar Pump & Supply License Number 3399

Address P.O. Box 209, Medicine Lodge, KS 67104

Company to plug at: Hour: 8 a.m. Day: 28 Month: 9 Year: 19 89

Plugging proposal received from Mike Farrar

(company name) Farrar Pump & Supply (phone) 316-886-3763

were: 4 1/2" at 5110' PBTB 5080' Perfs at 5060-68'

1st plug sand back to 5000' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:35 a.m. Day: 28 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 5000' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1989

10-2-89

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2600 of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-3-89

Signed Michael R. Wilson (TECHNICIAN)

INV. NO. 26014

DEC 15 1989