

To: 1051632
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-26

API NUMBER 15- 033-20,446-00-00

C SW SW, SEC. 21, T 33 S, R 20 W/EX

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30128

Lease Name Eubank Well # 21-13

Operator: Kenneth S. White

County Comanche 173.22

Name & Address 200 E. 1st, Ste. 210

Well Total Depth 5330 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 664

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 26 Month: 3 Year: 19 93

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 5328' w/150 sx cement, Perfs at 5245-65, 5033-41, 4808-12, 4790-4800'

1st plug pump 100 lbs. hulls and 30 sx cement and displace to 4600',

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 26 Month: 3 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 100 lbs. hulls and 30 sx common cement to 4600',

2nd plug pumped down the 8 5/8" pipe with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1

sx hulls, released 8 5/8" wiper plug and pumped 150 sx cement

Maximum pressure 500 psi and shut in 300 psi.

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1993
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 4000' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 4-1-93

Signed Richard M. Lauer (TECHNICIAN)

INV. NO. 37536