

To: 1 120723 8-6
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
600 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 15-151-10756-00 1003
SW SE SE, SEC. 25, T. 26 S, R. 13 W X
330 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118
Operator: TGT Petroleum Corporation
Name & Address: 209 E. William, Suite 615
Wichita, KS 67202

Lease Name Knop "B" Well # 2
County Pratt 140.30
Well Total Depth 4317 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 9:30 a.m. Day: 6 Month: 8 Year: 19 92

Plugging proposal received from Eldon Folmsbee

(company name) TGT Petroleum (phone) 316-262-6489

logs: 5 1/2" at 4313' w/250 sx cement, PBTD 4200', Perfs at 4234.5-39.5, 4229-32, 4216-22, 4261-66
4161-89, 3594-98, 3598-3608'

1st plug sand back to 3540' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 6 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 3483' and dumped 5 sx cement on top of sand
through bailer,

2nd plug pump in 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
and 100 sx cement.

Pumping pressure 200 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 1750' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

DATE 13 1992
8-13-92
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
I did observe this plugging.

DATE 9-11-92

Signed Duane Rankin (TECHNICIAN)

INV. NO. 36092