

To: 1 090795 3-28
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 033-20,073 - 00-00
C SW NW, SEC. 25, T 33 S, R 20 W/2
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5988
Operator: Halliburton Oil Producing Co.
Name:
Address 525 Central Park Dr.,
Central Park 1 #210
Oklahoma City, OK 73105

Lease Name Baker Well # 1
County Comanche 211.48
Well Total Depth 6507 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1118

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 28 Month: 3 Year: 19 97

Plugging proposal received from Manny Boatwright
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 4 1/2" at 5087' w/150 sx cement, Perfs at 4780-84'
1st plug sand back to 4725' and dump 4 sx cement on top of sand through bailer,
2nd plug at 1150' with 50 sx cement,
3rd plug at 500' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 p.m. Day: 28 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sand back to 4725' and dumped 4 sx cement on top of sand through bailer,
2nd plug pulled to 1180' and spotted 10 sx gel and 50 sx cement,
3rd plug pulled to 500' and spotted 50 sx cement,
4th plug pulled to 40' and circulated cement with 10 sx.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE 4-2-97
INV. NO. 47844

Signed [Signature] (TECHNICIAN)

RECEIVED
KANSAS CORP COM
197 APR - 2 PM 1:18