

1 051374

11-30

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,081-00-00
150' N of
C SW SW, SEC. 25, T 33 S, R 20 W/E

TECHNICIAN'S PLUGGING REPORT

810 feet from S section line
4620 feet from E section line

Operator License # 3062

Lease Name R. Baker Well # 1

Operator: Questa Energy Corporation
Name & Address: P.O. Box 19297
Amarillo, TX 79114

County Comanche 158.11
Well Total Depth 4865 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 13 3/8 feet 388

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10 a.m. Day: 30 Month: 11 Year: 19 90

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4863' w/150 sx cement, PBTD 4819', Perfs at 4783-4788'

1st plug set CIBP at 4240' with 20 sx cement on top,

2nd plug at 950' with 60 sx cement,

3rd plug at 410' with 90 sx cement,

4th plug at 40' with 20 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2 p.m. Day: 30 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4240' and dump 20 sx cement on top,

2nd plug at 950' with 60 sx cement,

3rd plug at 410' with 90 sx cement,

4th plug at 40' with 20 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 6 1990
12-06-90

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 3313' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

did not
~~observe~~ observe this plugging.

INVOICED

Signed Richard W. Lacey
(TECHNICIAN)

DATE 12-10-90

INV. NO. 30206

11-30

