

1 060048

11-26

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,255-00-00
NE SW SW, SEC. 25, T 33 S, R 20 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3062

Operator: Questa Energy Corporation
Name & Address: P.O. Box 19297
Amarillo, TX 79114

920 feet from S section line

4520 feet from E section line

Lease Name R. Baker Well # 2

County Comanche 158.27

Well Total Depth 4870 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 434

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 11:10 a.m. Day: 26 Month: 11 Year: 19 90

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 4864' w/175 sx cement, PBTD 4280', Perfs at 4214-4230'
1st plug pump 200 lbs. hulls and 25 sx cement,
2nd plug at 950' with 60 sx cement,

3rd plug at 460' with 70 sx cement,

4th plug at 40' with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2 p.m. Day: 26 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 25 sx cement,
Plugged through casing:

2nd plug at 950' with 60 sx cement,

3rd plug at 460' with 70 sx cement,

4th plug at 40' with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

12-03-90
DEC 3 1990

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 3656' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / observe this plugging.)

DATE 12-7-90

INV. NO. 30176

11-26

Signed Case M... (TECHNICIAN)

