

To: 1 090799 4-1  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 033-20,659-00-00  
C NW NW, SEC. 25, T 33 S, R 20  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5988  
Operator: Halliburton Oil Producing Company  
Name & Address: 525 Central Park Dr.  
Central Park 1 #210  
Oklahoma City, OK 73105

Lease Name Baker Well # 3  
County Comanche 159.59  
Well Total Depth 4849 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 598

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 1 Month: 4 Year: 1997

Plugging proposal received from Manny Boatwright  
(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

were: 4 1/2" at 4847' w/100 sx cement, Perfs at 4790-94'  
1st plug sand back to 4740' and dump 4 sx cement on top of sand through bailer,  
2nd plug at 1150' with 50 sx cement,  
3rd plug at 650' with 50 sx cement,  
4th plug at 40-0' with 10 sx cement.

RECEIVED  
KANSAS CORP COMM  
MAY 11 1997

Plugging Proposal Received by Steve Durran (TECHNICIAN)


Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:30 p.m. Day: 1 Month: 4 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 4740' and dumped 4 sx cement on top of sand through bailer,  
2nd plug at 1150' with 50 sx cement and 10 sx gel,  
3rd plug at 650' with 50 sx cement,  
4th plug at 40-0' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3500' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed  (TECHNICIAN)

DATE 4-8-97  
INV. NO. 47883