

1 060583

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,658-00-00

C SE NE, SEC. 26, T 33 S, R 20 W/R

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5988

Lease Name Schweitzer Well # 3

Operator: Halliburton Oil Producing Co.

County Comanche 158.28

Name & Address 2915 Classen Blvd.

Well Total Depth 4870 feet

Oklahoma City, OK 73106

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 597

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 12 Month: June Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4869' Perfs at 4805-10'

1st plug pump 50 sx cement to bottom

2nd plug shoot 4 1/2" at 260' and fill with cement

3rd plug pump 8 5/8" full of cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00 pm Day: 12 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement to bottom. 2nd plug shot pipe at

270' and pumped down 4 1/2" and circulated cement to surface on 8 5/8". 3rd plug put

swedge and valve on 4 1/2" and pumped down 8 5/8". Completed by pumping 150 sx cement

(50/50 Pozmix 2% gel 3% cc)

RECEIVED
STATE CORPORATION COMMISSION

Production casing collapsed at 260' - 8 5/8" pumped easily.

JUN 17 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 50/50 Pozmix 2% gel 3% cc by BJ-Titan. No recovery

If additional description is necessary, use BACK of this form.)

DATE (d10 / ~~xxxxxx~~) observe this plugging.

INV. NO. 8596

Signed Paul A. Luthi
(TECHNICIAN)