

1 060512

7-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C SW SW, SEC. 26, T 33 S, R 20 W/X  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-033-20,547  
660 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Willems "A" Well # 6

Operator: TXO Production Corp.

County Comanche 159.41

Name & Address: 200 W. Douglas, Suite 300

Well Total Depth 4905 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 683

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:45 am Day: 15 Month: March Year: 19 85

Plugging proposal received from Bill Faulds

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4901 PBTD 4869', Perfs at 4787-92'

1st plug pump 35 sx cement to bottom

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 135 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:00 am Day: 15 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 35 sx cement to bottom, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 135 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 25 1985

Maximum pressure 650 psi and shut in 400 psi

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. Recovered 2909 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

(did / ~~not~~) observe this plugging.

INVOICED

3-26-85

7462

Signed Paul A. Luthi (TECHNICIAN)