

1 051335

8-3

No docket # ever issued

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,567-00-01

C SE SW, SEC. 26, T 33 S, R 20 W/E

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Willems "A" Well # 5

Operator: TXO Production Corporation
Name & Address 1660 Lincoln Street, Suite 1800
Denver, CO 80264

County Comanche 160.88

Well Total Depth 4950 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 688

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1 p.m. Day: 3 Month: 8 Year: 19 90

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5606

were: 4 1/2" at 4940' w/350 sx cement, PBTD 4908' Perfs at 4826-32, 4468-84'

1st plug set CIBP at 4600' with 2 sx cement on top,

2nd plug sand back to 4350' and dump 4 sx cement on top of sand through bailer,

3rd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:10 p.m. Day: 3 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4600' with 2 sx cement on top,

2nd plug sanded back to 4350' and dumped 4 sx cement on top of sand through bailer,

3rd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and

150 sx cement.

Maximum pressure 600 psi and shut in 350 psi.

Also witnessed by Steve Middleton.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3100' of casing.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE: 8-23-90

INV. NO. 29029

Signed Richard W. Tracy
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1990
08-03-90
CONSERVATION DIVISION
Wichita, Kansas