

To: 1 090187 4-27  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-033-20,714-0000  
NW NW NW, SEC. 19, T. 32 S, R. 19 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 3536

4950 feet from S section line

4950 feet from E section line

Lease Name Lawrence Rich Well # 1

County Comanche

Operator: Ramco Energy Corporation  
Name & Address P.O. Box 340  
Great Bend, KS 67530

Well Total Depth 5245 170.46 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 678

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 5 p.m. Day: 27 Month: 4 Year: 19 92

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pulling (phone) 316-793-9711

were: 5 1/2" at 5243' w/125 sx cement, PBTD 5236', Perfs at 5129-33'

1st plug sand back to 5075' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 6 p.m. Day: 27 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 5075' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 450 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3046' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-6-92

INV. NO. 35168

Signed [Signature] (TECHNICIAN)

STATE CORPORATION COMMISSION  
RECEIVED  
CONSERVATION DIVISION  
Wichita, Kansas  
5-1-92