

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20581-0000

NW-NE Sec. 2, T 33 S, R 19 W

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6420

Lease Name Phillips Well # 1-2

Operator: K. R. M. Petroleum
Name & Address: 1900 Grant St. Suite 300
Denver Colo.
80203

County Comanche

Well Total Depth 5431 feet

Conductor Pipe: Size 16" feet 83'

Surface Casing: Size 8 1/8" feet 652

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co. License Number 5829 ^{tag 364}

Address P.O. Box 982 Pratt Kansas 67124

Company to plug at: Hour: 3:00 PM Day: 19 Month: 11 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Tom Harmon

(company name) Aldebaran Drilling Co (phone) _____

were: 1st plug @ 900' w/ 70 sbp cement. 2nd plug @ 400' w/ 40 sbp cement. 3rd plug on solid bridge @ 40' to 0' w/ 10 sbp cement. Then circulated 10 sbp cement in each the rat hole & mouse hole. The cement was pumped through drill pipe with hole full of mud. Halliburton cementing accomplished the plugging.
Signed Paul A. Luttin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:15 PM Day: 19 Month: 11 Year: 19 82

ACTUAL PLUGGING REPORT This hole was plugged as orders given in above paragraph.

RECEIVED
STATE CORPORATION COMMISSION
NOV 24 1982
11-24-82
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 12-23-82 Signed Paul A. Luttin
(TECHNICIAN)
INV. NO. 1918-W FORM CP-2/3
Rev. 9-82