

11-17-87

1040011

API NUMBER 15-033-20,003-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2 NE/4, SEC. 36, T 32 S, R 17 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3300 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5171

Lease Name Houseworth Well # 1
County Comanche 167.93

Operator: TXO Production Corporation
Name & Address 155 North Market, Suite 1000
Wichita, KS 67202

Well Total Depth 5167 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 414

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 17 Month: 11 Year: 19 87

Plugging proposal received from Allen Dick

(company name) TXO Production Corporation (phone) 316-886-5606

were: 2 7/8" at 5167' Perfs at 5105-09, 5118-28, 5132-36' Elevation 1989' GL

1st plug pump 200 lbs. hulls and 10 sx cement,

2nd plug pump 3 sx hulls and 150 sx Thrifty Mix with 2 sx hulls mixed in.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:20 a.m. Day: 17 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped down 2 7/8" casing with 200 lbs. of hulls and 10 sx cement. Pressured to 2000 psi. (B.J. Titan - common cement)

2nd plug pumped down 8 5/8" surface casing with 300 lbs. hulls ahead of cement and 200 lbs. of hulls in with first of cement. Pumped 150 sx cement. Pumping pressure 100-450 psi and shut in 300 psi. (B.J. Titan - Thrifty Mix)

RECEIVED
NOV 19 1987
11-19-87

Remarks: Used common cement and Thrifty Mix by B.J. Titan. Recovered 2500' of 2 7/8" casing. (if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Stephen J. Pfeiffer (TECHNICIAN)

DATE 12-3-87

INV. NO. 19073