

1100359

TO: STATE CORPORATION COMMISSION

API NUMBER 15-033-21,090 -- 00-00  
C NE NE SEC. 17, T 32 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BERGNER "C" WELL # 17-1

TECHNICIAN'S PLUGGING REPORT

COUNTY COMANCHE 173.71

OPERATOR LICENSE # 3869

WELL TOTAL DEPTH 5345 FEET

OPERATOR: IMPERIAL OIL PROPERTIES PRODUCTION CSG: SIZE @ ' WITH SX

NAME AND 200 E 1ST ST., #413 SURFACE CASING: SIZE 8 5/8" @ 686' WITH SX

ADDRESS WICHITA, KS 67202 CONDUCTOR CSG: SIZE 20" @ 40'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR VAL ENERGY LICENSE NUMBER 5822

ADDRESS PO BOX 116 WICHITA, KS 67201

COMPANY TO PLUG AT: HOUR: 5:30 AM DAY: 07 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM SKIP

(COMPANY NAME) VAL ENERGY (PHONE) 316-263-6688

WERE:

1ST PLUG AT 1110' WITH 50 SX CEMENT. 2ND PLUG AT 700' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 8:30 AM DAY: 07 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1110' WITH 50 SX CEMENT. 2ND PLUG AT 700' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

RECEIVED STATE CORPORATION COMMISSION 06-22-2000 JUN 22 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING.

INVOICED DATE 6/27/00 SIGNED 61898

GARY WINTERS (TECHNICIAN)

FORM CP-2/3

Handwritten initials and signature