

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20951-00-~~00~~01 ^{KCC} ^{apb} 4-28-09
Spot: SESESE Sec/Twnshp/Rge: 17-32S-18W
482 feet from S Section Line, 482 feet from E Section Line
Lease/Unit Name: WILLBANKS Well Number: 17-1
County: COMANCHE Total Vertical Depth: 5800 feet

Operator License No.: 3869
Op Name: IMPERIAL OIL PROPERTIES, INC.
Address: 200 E FIRST ST., SUITE #413
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1080 WITH 325 SX CMT
Production: Size 5.5 feet: 5296 WITH 100 SX CMT
Liner: Size feet: 188.50

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/13/2000 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SET CIBP @ 5000' & 2 SX CMT ON TOP. 1ST PLUG AT 1100' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. USE 10 SX GEL FOR GEL SPACER.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/13/2000 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 5056-61, 5101-11, 5195-5200, 5202-04, & 5208-14. SET CIBP @ 5000' AND PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1100' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION
12-18-2000
DEC 18 2000

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 3720' OF 5 1/2" CASING WICHITA, KS

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 12/18/00

INV. NO. 2001061151

DEC 14 2000

Form CP-2/3