

1060271

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,656-00-00
150' E of C
SE NW, SEC. 27, T 32 S, R 20
1980 feet from N/E section line
2130 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6677

Lease Name Peterson Well # 1 A

Operator: Sandlin Oil Corporation
Name & Address: 2300 Security Life Building
Denver, CO 80202

County Comanche

Well Total Depth 5300 172.25 feet

Conductor Pipe: Size 10 3/4 feet 164

Surface Casing: Size 8 5/8 feet 724 600

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 10:00 am Day: 18 Month: July Year: 19 84

Plugging proposal received from Tom Harmon

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1000' with 50 sx cement

2nd plug at 280' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plug water well with 5 sx cement Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None X

Operations Completed: Hour: 1:00 pm Day: 18 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1000' with 50 sx cement, 2nd plug at 280' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate mouse hole with 10 sx cement, and plugged water well with 5 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form)

observe this plugging.

INVOICED

DATE 7-27-84

INV. NO. 2201

Signed Paul A. Luthi (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 7-24-84 JUL 24 1984 CONSERVATION DIVISION Wichita, Kansas