

R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21197-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 23-32S-20W
2111 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: MCMILLEN TWIN Well Number: 1
County: COMANCHE Total Vertical Depth: 6160 feet

Operator License No.: 31514
Op Name: THOROUGHbred ASSOCIATES L.L.C.
Address: 8100 E. 22ND ST. - BUILDING 600
WICHITA, KS 67226

Conductor Pipe: Size 20 feet: 103 # 20020
Surface Casing: Size 8.625 feet: 842
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 03/02/2001 3:15 PM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 870' WITH 50 SX CMT. 2ND PLUG AT 350' WITH 25 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 03/02/2001 4:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

1ST PLUG AT 870' WITH 50 SX CMT. 2ND PLUG AT 350' WITH 25 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

INVOICED

DATE 03-08-2001

INV. NO. 200/061470

RECEIVED
STATE CORPORATION COMMISSION

MAR 6 2001
3-6-01


Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: DP

District: 01


Signed



(TECHNICIAN)

MAR 05 2001

MP



ALLIED CEMENTING CO., INC. 4545

Federal Tax I.D.# 48-0727860

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
med. lodge, ks.

DATE <u>3-2-01</u>	SEC. <u>23</u>	TWP. <u>36s</u>	RANGE <u>20w</u>	CALLED OUT <u>7:00 A.M.</u>	ON LOCATION <u>11:00 P.M.</u>	JOB START <u>3:15 P.M.</u>	JOB FINISH <u>4:30</u>
LEASEM <u>Miller</u>	WELL #	LOCATION <u>Coldwater Car Wash</u>			COUNTY <u>Comanche</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)			<u>8w-1s-2/s</u>				

CONTRACTOR Pickrell Drng.
 TYPE OF JOB Rotary Plug
 HOLE SIZE 7 7/8 T.D. 6160'
 CASING SIZE 8 5/8 DEPTH 842
 TUBING SIZE DEPTH
 DRILL PIPE 4 1/2 x hole DEPTH 870'
 TOOL DEPTH
 PRES. MAX 150 MINIMUM 100
 MEAS. LINE SHOE JOINT
 CEMENT LEFT IN CSG.
 PERFS.
 DISPLACEMENT Fresh H₂O
 EQUIPMENT
 PUMP TRUCK CEMENTER Larry Dreiling
 # 343 HELPER Larry Dreiling
 BULK TRUCK
 # 261 DRIVER Jason Tritt
 BULK TRUCK
 # DRIVER

OWNER Thoroughbred + Associates
 CEMENT
 AMOUNT ORDERED 110SX 60/40/6%Gel
 COMMON A 66 @ 6.35 419.10
 POZMIX 44 @ 3.25 143.00
 GEL 6 @ 9.50 57.00
 CHLORIDE @
 @
 @
 @
 @
 @
 @
 @
 @
 HANDLING 116 @ 1.05 121.80
 MILEAGE 116 x 49 .04 227.36
 TOTAL 968.26

REMARKS:
870' - 50SX
350' - 25SX
40' - 10SX
MH - 10SX
RH - 15SX
Cemented w/ 110sx 60/40/6%Gel

SERVICE
 DEPTH OF JOB 870'
 PUMP TRUCK CHARGE 470.00
 EXTRA FOOTAGE @
 MILEAGE 49 @ 3.00 147.00
 PLUG @
 @
 @

TOTAL 617.00

CHARGE TO: Thoroughbred + Associates
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT
 @ _____
 @ _____
 @ _____
 @ _____
 @ _____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE 1585.26
 DISCOUNT 158.53 IF PAID IN 30 DAYS

SIGNATURE X Mike Kern X Mike Kern
 RECEIVED 1426.73
 PRINTED NAME

AUG - 8 2001
 KCC WICHITA