

1 051694

7-13

API NUMBER 15- 033-20,842 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 SW SE, SEC. 28, T. 33 S, R. 16 WXX
555 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5278

Lease Name Merrill Ranch Well # 1-28

Operator: Enron Oil & Gas Company

County Comanche

Name & Address 20 N. Broadway, Ste. 830

Well Total Depth 5098 165.68 feet

Oklahoma City, OK 73102

Conductor Pipe: Size 10 3/4 feet 211

Surface Casing: Size 8 5/8 feet 1209

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 12 p.m. Day: 13 Month: 7 Year: 19 93

Plugging proposal received from Fred Mease

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 5093' w/225 sx cement, Perfs at 4974-84'

1st plug set CIBP at 4900' with 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 13 Month: 7 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4900' and dumped 2 sx cement on top, 2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 800 psi and shut in 400 psi.

RECEIVED STATE CORPORATION COMMISSION

MAR 16 1993 7-16-93 CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3800' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE: 2-28-93

Signed Richard M. Lucas (TECHNICIAN)

INV. NO. 3P210