

To: 1 05 609
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-12

API NUMBER 15- 033-20,694-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 4570
Operator: Samedan Oil Corp.
Name & Address: 3817 N.W. Expressway, Ste. 1020
Oklahoma City, OK 73112

SW SW, SEC. 28, T. 32 S, R. 19 W/E
660 feet from S section line
4620 feet from E section line
Lease Name Bird Well # 1-28
County Comanche 173.23
Well Total Depth 5330 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 886

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 12 p.m. Day: 12 Month: 1 Year: 1993
Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 5 1/2" at 5330' w/175 sx cement, PBTD 5283', Perfs at 5086-5234'
1st plug pump 2 sx hulls and 20 sx cement to bottom,
2nd plug pump 60 sx cement at 4100', 3rd plug pump 50 sx cement at 900',
4th plug pump 40 sx cement at 450', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5 p.m. Day: 12 Month: 1 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to bottom,
2nd plug at 4100' with 60 sx cement,
3rd plug at 900' with 50 sx cement,
4th plug at 450' with 40 sx cement,
5th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 4200' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
1-17-93
JAN 19 1993
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
I did observe this plugging.
DATE 1-25-93
INV. NO. 37240

Signed Richard M. Lacy (TECHNICIAN)

15-633-10674-0000

GEARHART

DUAL INDUCTION
LATEROLOG

FILING NO. 351751 7661-103		COMPANY SAMEAN OIL CORPORATION		WELL BIRD # 1-28		FIELD S.W COLDWATER		COUNTY COMANCHE		STATE KANSAS		
LOCATION: 660' FS. & 690' FWL		SEC 28		TWP 32 S		RGE 19 W		Other Services MEL/GR CDL/CNL				
Permanent Datum GL		Elev. 1912		Elev.: K.B. 1924		Log Measured from KB		12 Ft. Above Perm. Datum		D.F. 1922		
Drilling Measured from KB				G.L. 1912								
Date	1-24-86											
Run No.	ONE											
Depth-Driller	5300											
Depth-Logger	5292											
Bottom Logged Interval	5290											
Top Logged Interval	887											
Casing-Driller	85/8 @ 886											
Casing-Logger	887											
Bit Size	7/8											
Type Fluid in Hole	LSD											
Density	9.3		46									
ph	12		11		cc		cc		cc		cc	
Source of Sample	MUD PIT											
Rm @ Meas. Temp.	1.38 @ 56 °F											
Rmf @ Meas. Temp.	0.87 @ 59 °F											
Rmc @ Meas. Temp.	1.78 @ 59 °F											
Source of Rmf	M		M									
Rm @ BHT	0.63 @ 121 °F											
Time	End Circulation		14:30									
	Logger on bottom		17:57									
Max Rec. Temp. Deg. F.	121 °F											
Equip. No.	7661		W.W									
Recorded By	TRUONG											
Witnessed By	MR BUSHMAN, MR KELLER											

**FIELD
PRINT**