

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-033-20,567-00.01 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR TXO Production Corp. OPERATOR'S LICENSE NO. 5171

ADDRESS 1660 Lincoln St., Ste 1800, Denver, CO 80264 PHONE # (303) 861-4246

LEASE (FARM) Willems "A" WELL NO. 5 WELL LOCATION 660' FSL & 1980' FWL COUNTY Comanche

SEC. 26 TWP. 33S RGE. 20 ~~W~~ W TOTAL DEPTH 4950' PLUG BACK TD 4908'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. None Assigned

SURFACE CASING SIZE 8-5/8" SET AT 688' CEMENTED WITH 450 SACKS

CASING SIZE 4-1/2" SET AT 4940' CEMENTED WITH 350 SACKS

PERFORATED AT 4826'-32', Swope - Injection zone

4468'-84' Lansing - Kansas City, - Water Source zone.

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ ± 4600'. Fill 4-1/2: csg w/ sand to ±4350'.

Dump bail 3 sxs of cement on top. Pull ± 3500' of 4 1/2" csg. Plug 8-5/8" w/ 5 sxs hulls,

50 sxs 60-40 poz, 2 sxs hulls, 25 sxs 60-40 poz. Cut off 8-5/8" csg. 6' below ground.

Cap with welded plate. (If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Logs on IS ACO-1 FILED? Yes
(If not explain.) Record

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be co-ordinated between TXO and KCC field personnel.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leamon Roberson PHONE # (316) 886-5606

ADDRESS P. O. Box 125B, Medicine Lodge, Kansas 67104

PLUGGING CONTRACTOR Clarke Corporation LICENSE NO. 5105

ADDRESS 107 W. Fowler, Box 187, Medicine Lodge, KS PHONE # (316) 886-5606

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

①
MAR 15 1990
03-15-90
CONSERVATION DIVISION
Wichita, Kansas

SIGNED:

Walter Coy West
(Operator or Agent)

DATE:

2-12-90



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE
JUN 27 1990
EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

March 27, 1990
NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

TXO Production Corp.
1660 Lincoln St., Ste 1800
Denver, CO 80264

Willems "A" 5
660'FSL-1980'FWL
Sec. 26-33-20W
Comanche County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760