

TATE OF KANSAS  
TATE CORPORATION COMMISSION  
30 S. Market, Room 207B  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

KCC 019-09  
4-28-09  
API NUMBER 15-033-20951-00

LEASE NAME Willbanks

WELL NUMBER 17-1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

         Ft. from S Section Line

         Ft. from E. Section Line

SEC. 17 TWP. 32S RGE. 18W (E) or (W)

LEASE OPERATOR IMPERIAL OIL PROPERTIES, INC.

ADDRESS 200 E. First St. #413 Wichita, Kansas 67202

COUNTY Comanché

PHONE# (316) 263-5596 OPERATORS LICENSE NO. 3869

Date Well Completed         

Character of Well Oil

Plugging Commenced 12-6-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-13-00

The plugging proposal was approved on          (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 5800'

Show depth and thickness of all water, oil and gas formations.

RECEIVED

OIL, GAS OR WATER RECORDS | CASING RECORD KANSAS CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1080'	None
				5-1/2"	5296'	3830'

12-28-2000  
DEC 28 2000  
CONSERVATION DIVISION  
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each. Set CIBP @5000' with 2 sks. cement on top. Shot pipe @4700', 4500', 4000' and 3830'. Pulled up to 1100', pumped 50 sks. cement and 10 sks. gel, pulled up to 550', pumped 40 sks. cement, pulled up to 40', pumped 10 sks. cement, 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Imperial Oil Properties, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 26th day of December, 2000

James Steinhilber  
Notary Public

My Commission Expires:         



Form CP  
Revised 05-