

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-033-20,849-00-01

LEASE NAME MERRILL RANCH

WELL NUMBER 28-2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

550 Ft. from S Section Line

1050 Ft. from E Section Line

SEC. 28 TWP. 33 RGE. 16 (W)

LEASE OPERATOR ENRON OIL & GAS CO.

ADDRESS 20 N. BROADWAY #830 OKLAHOMA CITY, OK 73102

COUNTY COMANCHE

PHONE#(405) 239-7800 OPERATORS LICENSE NO. 5278

Date Well Completed _____

Character of Well GAS

Plugging Commenced 6-23-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-13-93

The plugging proposal was approved on JULY 9, 1993 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5038

Show depth and thickness of all water, oil and gas formations. ...

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	214	10 3/4	214	0
		0	5038	4 1/2	5038	3652 FT, 86 JTS.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

SET CIBP AT 4800 FT., DUMPED SAND & 2 SX. CEMENT ON TOP. SHOT CASTING OFF AT 3652, PULLED 86 JTS. TOP OF CEMENT AT 3850. TOP HOLE PLUGGED WITH 300# HULLS, 10 SX. GEL, 50 SX. CEMENT, 10 SX. GEL, 100# HULLS, WIPER PLUG, 175 SX. CEMENT, 60-40 POZ, 6% GEL. MAX 200#, ISIP100#.
ALLIED CHECKED TOP OF CEMENT, 2 FT. DOWN FROM SURFACE, FILLED WITH SAND AND DIRT.
 (If additional description is necessary, use back of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, ICN. License No. 5893

Address P O BOX 847 PRATT, KANSAS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ENRON OIL & GAS CO.


STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY

PLUGGING CONTRACTOR

(Employee of ~~OPERATOR XXXXXXXXXXXXXXXXXXXX~~)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry
 (Address) PRATT WELL SERVICE, INC.



SUBSCRIBED AND SWORN TO before me this 26th day of July 1993

Dorothy M. Furgason Notary Public
 My Commission Expires February 6, 1997

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 26 1993
 CONSERVATION DIVISION
 Wichita, Kansas