

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-033-20,842-00-00

LEASE NAME MERRILL RANCH

WELL NUMBER 1-28

550 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 28 TWP. 33 RGE. 16 ~~WEST~~ (W)

COUNTY COMANCHE

Date Well Completed _____

Plugging Commenced 6-19-93

Plugging Completed 7-13-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR ENRON OIL & GAS CO.

ADDRESS 20 NORTH BROADWAY #830 OKLAHOMA CITY, OK. 73102

PHONE# (405) 239-7800 OPERATORS LICENSE NO. 5278

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on JULY 9, 1993 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5098

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	211	10 3/4	211	0
		0	1209	8 5/8	1209	0
		0	5093	4 1/2	5093	89 JTS. 3800 FT.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

SET CIBP AT 4900. DUMPED SAND AND TWO SX. CEMENT, AFTER PULLING 160 JTS. OF 2 3/8 TUBING.
SHOT CASING OFF AT 3800, PULLED 89 JTS. TOP HOLE PLUG: 300# HULLS, 10 SX. GEL, 50 SX. CEMENT,
10 SX. GEL, 100# HULLS, WIPER PLUG, 150 SX. CEMENT, 60-40 POZ. 6% GEL, 800# MAX, 400# ISIP.
1:15PM. ALLIED CHECK TOP OF CEMENT, WAS 3 FT. DOWN FROM SURFACE, FILLED IN WITH SAND & DIRT.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KANSAS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ENRON OIL & GAS CO.

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR

(Employee of ~~XXXXXXXXXXXXXXXXXXXX~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PRATT WELL SERVICE, INC.



SUBSCRIBED AND SWORN TO before me this 26th day of July

Dorothy M. Ferguson Notary Public

My Commission Expires: February 6, 1997

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 28 1993
 CONSERVATION DIVISION
 Wichita, Kansas
 Revised 05-88