

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 5033-20694-0000

LEASE NAME Bird

WELL NUMBER 1-28

660 Ft. from S Section Line

4640 Ft. from E Section Line

SEC. 28 TWP. 32S RGE. 19W (E) or (W)

COUNTY Comanche

Date Well Completed 3/11/86

Plugging Commenced 1/12/93

Plugging Completed 1/12/93

LEASE OPERATOR Samedan Oil Corporation

Suite 1020, 3817 N.W. Expressway

ADDRESS Oklahoma City, Oklahoma 73112

PHONE# (405) 942-8707 OPERATORS LICENSE NO. 4570

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1 (316) 225-6760

Is ACO-1 filed? Yes If not, is well log attached? NA

Producing Formation Mississippi Depth to Top 5097 Bottom 5300 T.D. 5330

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	Gas	5097	5300	8 5/8	886'	0'
				5 1/2	5330'	4205'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

0 psi on well. Pull 1 jt 5 1/2" csg & spot end of casing @ 950', mixed & pumped 50 sxs "H" @ 15.5 ppg w/ yield of 1.22 ft3/sx. Balanced 164' cmt plug from 950' to 786' (surface csg set @ 886'), 64' below surface, and 100' in surface. RD cementers; POOH w/ 5 1/2" csg to 450'. Mix and pump 40 sxs "H" @ 15.5 ppg w/ yield of 1.22 ft3/sx. Balanced 100' plug from 450' to 350'.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent Casing Pulling License No. 1-15-93

Address 620 South Lincoln, Liberal, KS 67901

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

RECEIVED OVER
 CORPORATION COMMISSION
 JAN 15 1993
 CONSERVATION DIVISION
 WICHITA, KANSAS

I, Debbie Kerr, (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Debbie Kerr
 (Address) Ste. 1020, 3817 N.W. Expressway Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 13th day of January, 19 93

Karen Lannox
 Notary Public

My Commission Expires: March 16, 1995

POOH, finish LD 5 1/2" casing. PU 1 jt 2 3/8" tbg & sub. RIH & spot tbg @ 40', mix and pump 10 sxs Class "H" @ 15.5 ppg w/yield of 1.22 ft³/sx for 36'. Surface plug from 40' to 4'. POOH w/tbg, cut off surface casg & cap. Mark cap - Samedan Oil Corp, Bird 1-28, Section 28-32S-19W. 1/12/93. Plugging procedure recommended by Steve Middleton w/KCC. Plug @ surface casing depth to surface casing top plug witnessed by Richard Lasey with KCC. All plugging in accordance w/KCC rules per Richard Lacey. Recovered 101 jts 5 1/2" 17# J-55, LTC casing, total 4205'.