

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

RECEIVED  
STATE CORPORATION COMMISSION  
9-30-81  
SEP 30 1981  
CONSERVATION DIVISION  
Wichita, Kansas

Give All Information Completely  
Make Required Affidavit

COUNTY Comanche SEC. 20 TWP. 33S RGE. 16 E/W  
Location as in quarters or footage from lines:  
E/2 E/2 NW/4


Lease Owner Mid-Continent Energy Corporation  
Lease Name Gregg 1-20 Well No. 1  
Office Address 712 One Twenty Building, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 9/8/81  
Application for plugging filed 9/8/81  
Plugging commenced 9/8/81  
Plugging completed 9/8/81 10:15 p m  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 5097'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	1018'	8-5/8"	yes	no
		0	149'	13-3/8"	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

1st plug @ 1620' with 60 sacks  
2nd plug @ 1000' with 50 sacks  
3rd plug @ 400' with 30 sacks  
Bridge @ 40' with 10 sacks  
10 sacks in rathole  
Job complete @ 10:15 p.m. 9/8/81

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Slawson Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

James C. Remsberg, Slawson Drilling (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg  
200 Douglas Building, Wichita 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of September, 19 81



Mary Lou Taylor  
Mary Lou Taylor Notary Public.

My Commission Expires: January 17, 1985

DRILLERS LOG

RECEIVED  
STATE CORPORATION COMMISSION

SEP 30 1981

CONSERVATION DIVISION  
Wichita, Kansas

OPERATOR: Mid-Continent Energy Corp.  
712 One Twenty Building  
Wichita, Kansas 67202

WELL NAME: #1-20 Gregg  
E/2 E/2 NW/4 Sec.20-33S-16W  
Comanche County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
200 Douglas Building  
Wichita, Kansas 67202

COMMENCED: 8/25/81

COMPLETED: 9/8/81

RTD: 5097'

SURFACE CASING: 8-5/8" set at 1018' with 550 sx cement  
13-3/8" set at 149' with 175 sx cement

0' to 579' Red Bed- Shale  
579' to 3000' Shale  
3000' to 4623' Shale & Lime  
4623' to 5097' Lime & Shale  
RTD 5097'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state the above is an accurate copy of the #1-20 Gregg log for Mid-Continent Energy Corp.

*James C. Remsberg*  
James C. Remsberg

Subscribed and sworn to me  
this 18th day of September, 1981

*Mary Lou Taylor*  
Mary Lou Taylor, Notary

My commission expires January 17, 1985

