

15-151-10873-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Pratt County. Sec. 36 Twp. 26 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NW SW

Lease Owner McKnab Drilling, Inc.

Lease Name Beck Well No. 1

Office Address 605 Union Natl. Bank Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 17 19 55

Application for plugging filed April 17 19 55

Application for plugging approved April 17 19 55

Plugging commenced April 17 19 55

Plugging completed April 17 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4370 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red Bed	Surface	0	457	8 5/8	4-3-55	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Gunned up pits circ. heavy mud - layed down drill pipe - filled hole with mud to 300'  
Set Howco Top plug with hulls - mixed 20 sacks cement through 10 joints drill pipe -  
filled hole with mud to 35' - set Howco plug with hulls and tied with wire line -  
cement with 10 sacks cement on top of plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_

Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Don Gardner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

605 Union Natl. Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of April, 1955

[Signature] Notary Public.

My commission expires November 21, 1956

**PLUGGING**  
FILE SEC 361-26-134  
BOOK PAGE 112 LINE 6



**RECEIVED**  
STATE CORPORATION COMMISSION

APR 28 1955  
4-28-55  
CONSERVATION DIVISION  
Wichita, Kansas

15-151-10873-00-00

D R I L L E R ' S L O G

McKnab Drilling, Inc.

NE Beck #1

NE NW SW 36-26-13W

Pratt County, Kansas

<u>TO</u>	<u>FROM</u>	
0	275	Sand
275	370	Red Bed & Shale
370	845	Red Bed, Shale & Shells
845	1005	Shale & Red Bed
1005	1320	Shale & Shells
1320	1660	Sand & Shale
1660	1845	Shale, Shells & Lime
1845	1940	Shale & Shells
1940	2050	Shale & Lime
2050	2160	Shale & Lime
2160	2370	Lime
2370	2450	Lime & Shale
2450	3315	Shale & Lime
3315	3393	Lime & Shale
3393	3588	Shale & Lime
3588	3692	Sand, Shale & Lime
3692	3798	Shale & Lime
3798	4245	Lime
4245	4275	Shale & Sand
4275	4321	Sand & Shale
4321	4350	Shale & Lime
4350	4370	Lime
	4370	ROTARY TOTAL DEPTH
		D & A

COMMENCED: 4-1-55  
COMPLETED: 4-17-55


CASING RECORD

Set 457' of 8 5/8" surface casing with 300 sacks of cement, 1% c.c. and 2% jell.


STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Beck #1 located in the NE NW SW of Section 36, Township 26 South, Range 13 West, Pratt County, Kansas.

MC KNAB DRILLING, INC.

  
Don Gardner

Subscribed and sworn to before me this 26th day of April 1955.

  
Helen S. Lang  
Notary Public

My Commission Expires November 21, 1956

**PLUGGING**  
FILE SEC 36-26-13W  
PAGE 1/2 LINE 6

RECEIVED  
STATE CORPORATION COMMISSION  
APR 29 1955  
CONSERVATION DIVISION  
Wichita, Kansas