

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Nichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-003-20.659-00-00

LEASE NAME Baker

WELL NUMBER 3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 25 TWP. 33s RGE. 20W (E) or (W)

COUNTY Comanche

Date Well Completed

Plugging Commenced 3-31-97

Plugging Completed 4-01-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

LEASE OPERATOR Halliburton Oil Producing Co.

525 Central Park Dr.

ADDRESS Central Park 1 #210 Oklahoma City, OK 73105

PHONE# (405) 525-3371 OPERATORS LICENSE NO. 5988

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4849'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	598'	none
				4 1/2	4847'	3505'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each side. Sanded off bottom to 4716' & ran 4 sks cement. Shot at 3505', worked pipe loose. Pulled to 1150', pumped 10 gel & 50 sks cement. Pulled to 650', pumped 50 sks cement. Pulled rest of pipe, topped off. Plugging complete. 60/40 poz 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Halliburton Oil Producing Co.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 11th day of April, 19 97

[Signature]
Notary Public

My Commission Expires:



RECEIVED
KCC DISTRICT AGENT
APR 14 A 11:55