

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Comanche County, Sec 10 Twp 33 Rge #16 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE/4

Lease Owner Phillips Petroleum Co.

Lease Name Comanche Well No. 1

Office Address Bartlesville, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 7-17-44 19

Application for plugging filed 7-17-44 19

Application for plugging approved 7-17-44 19

Plugging commenced 7-18-44 19

Plugging completed 7-18-44 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top 5577 D.F Bottom 5604 DF Total Depth of Well 5604 DF Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Anhydrite	Dry	1083 DF		10 3/4"	1082 (OA)	None
Lans KC	Dry	4226 DF				
Mississippi	Dry	4856 DF				
Kinderhook	Dry	5163 DF				
Viola	Dry	5261 DF				
Simpson	Dry	5420 DF				
Arbuckle	Dry	5577 DF				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud to 1084, ran 25 sacks cement @ 1084, filled with mud to 30', ran 25 sacks cement filling to base of cellar.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to F. W. Shelton

Address Box 779 Great Bend, Kans.

STATE OF Kansas, COUNTY OF Barton, ss.

F. W. Shelton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. W. Shelton

Box 779 Great Bend, Kans.

(Address)

SUBSCRIBED AND SWORN to before me this 17th day of August, 19 44

My commission expires January 20, 1945

Gertrude Hochstatter
Notary Public.

8-13-44


Formation Record

Lease Comanche

Well No. 1

FROM	TO	Formation	REMARKS
0	60	Clay & red bed	Elevation 1774 D.F.
60	180	Red bed	
180	380	Red rock	
380	670	Red bed	
670	950	Gyp & red bed	
950	1080	Red rock & shale	
1080	1080	Red rock	
1080	1094	Lime	
1094	1105	Anhydrite	Top Anhydrite 1083 D.F.
1105	1400	Shale & sand	
1400	1990	Shale & shells	
1990	2050	Lime	
2050	2080	Broken lime	
2080	2125	Lime & gyp	
2125	2215	Sandy lime	
2215	2300	Lime & flint	
2300	2320	Shale & shells	
2320	2455	Lime & shale	
2455	2575	Sandy lime	
2575	2625	Lime & shale	
2625	2690	Shale & shells	
2690	2835	Shale & lime	
2835	2880	Shale & shells	
2880	2990	Lime & shale	
2990	3018	Lime	
3018	3460	Lime & shale	
3460	3474	Chert & lime	
3474	3640	Lime	
3640	3684	Lime & shale	
3684	3708	Lime	
3708	3710	Shale	
3710	3736	Shale & lime	
3736	3750	Lime	
3750	3836	Shale & lime	
3836	3900	Broken lime & shale	
3900	3948	Lime & shale	
3948	4048	Shale	
4048	4330	Lime	Top LKC 4226' D.F.
4330	4379	Lime & shale	
4379	4510	Lime	
4510	4595	Lime & shale	
4595	4840	Lime	
4840	4875	Lime & chert	Top Miss. 4656' D.F.
4875	4900	Lime	
4900	4915	Broken lime & chert	

(contd.)



Formation Record

Lease **Comanche**

Well No. **1**

FROM	TO	Formation	REMARKS
4915	4925	Line & chert	
4925	5065	Line	
5065	5080	Line & shale	
5080	5115	Line	
5115	5149	Line & shale	
5149	5183	Line	Top Kinderhook 5163 D.F.
5183	5195	Shale	
5195	5265	Line & shale	
5265	5325	Line	Top Viola 5261 D.F.
5325	5353	Cherty line	
5353	5364	Line & chert	
5364	5383	Line	
5383	5390	Cherty line	
5390	5413	Line	
5413	5491	Line & chert	Top Simpson 5420 D.F.
5491	5475	Line	
5475	5485	Line & shale	
5485	5521	Sandy lime & shale	
5521	5545	Sand & lime	
5545	5570	Line & shale	
5570	5578	Shale & sand	Top Arbuckle 5577 D.F.
5578	5604	Line	

BL LOGGING
 FILE 10 33-1600
 BOOK PAGE 124 LINE 32