

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20641-00-01

LEASE NAME Kimble

WELL NUMBER 1

3690 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 35 TWP. 32S AGE. 18W (E) or (W)

COUNTY Comanche

Date Well Completed 5-14-84

Plugging Commenced 11-15-94

Plugging Completed 11-16-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR American Energies

ADDRESS 155 N. Market Wichita, Ks. 67202

PHONE (316) 263-5785 OPERATORS LICENSE NO. 5399

Character of Well _____

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ District 1 (date)
by Steve Middleton (XCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Vilola Depth to Top 5611 Bottom _____ T.O. 5740

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	568	8 5/8	568	none
		0	5740	5 1/2	5738	3470

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Tubing was cemented in from Viola to 4831 ft. Shoot off tubing at 4831 ft.
Shot off casing at 3470 ft, and laid down. Pumped 300lbs hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs hulls, wiper plug, 150 sx cement.
60/40 Pozmix 6% Gel. Allied Ticket # 843

Name of Plugging Contractor VAL Energy Inc.

License No. 5822

Address Box 322 Hasyville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Energies

STATE OF Kansas COUNTY OF Sedgwick, ss.

Todd Allam/ Agent

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Todd Allam

(Address) Wichita, Ks.

SUBSCRIBED AND SWORN TO before me this 18 day of November, 19 94

USE ONLY ONE SIDE OF EACH FORM

My Commission Expires:



Form CP-4
Revised 05-88

AMERICAN ENERGIES CORPORATION

WELL WORKOVER REPORT

Lease	Kimble	Surface Casing	8 5/8" @ 568'
Location	Section 35-T32S-R18W	Production Casing	5 1/2" @ 5738'
County	Comanche	Elevation	2015 K.B.
Operator	American Energies Corp.	Spud	3/31/84 Completion

1/03/92 MIWU. Picked up washover pipe went in hole to recover tubing. Tripped into hole with 3000' 2 3/8" tubing, 330' 4 1/2" washover pipe with mechanical cutter. SDON.

1/04/92 Washedover 325' 2 3/8" tubing, cut off, came out laying down 325' 2 3/8" tubing. SDON.

1/05/92 Tripped in hole with tubing washover pipe, washedover 292' 2 3/8" tubing. Cut off, came out laying down 2 3/8" tubing. SD for Sunday.

1/06/92 Shut down for Sunday.

1/07/92 Finishing tripping out with fish. Picked up washover pipe and shoe mill. Started tripping into hole.

1/08/92 Finishing tripping into hole. Started washover fish at 4791'. Washed over to 4831'. Would not cut any more. Tripped out with washover pipe and mill. Mill was worn out. Tripped back in hole with washover pipe and new mill. Started washing over fish. SDON.

1/09/92 Washed over and milled to 4848. Stuck washover pipe and mill worked loose. Tripped out of hole to check washover pipe and mill. SDON.

1/10/92 Tripped in hole with new mill and washover pipe. Started milling of fish, cut 2 1/2' in three hours. Started tripping out of hole.

1/11/92 Finished tripping out of hole. Laid down washover pipe and tubing. Released rig. Will pool partners Monday 1/13/92. Cost to date: \$21,500.

B-J

1/19

PBTD 4831
Cmt Tubing in hole

RECEIVED
STATE CORPORATION COMM

SEP 21 1994

WICHITA KANSAS